

	Development and Production Operations Service CONTRACT for Sohrab Oil Field Well pad Construction (3,4,8) Tender No.: SO-004-00082-03	 DanaEnergy
Rev. 00	Document No. SO-082-DTE-LGN-BD-CFT-0001	Page 1 of 61

SECTION 6

HSE

	Development and Production Operations Service CONTRACT for Sohrab Oil Field Well pad Construction (3,4,8) Tender No.: SO-004-00082-03	 DanaEnergy
Rev. 00	Document No. SO-082-DTE-LGN-BD-CFT-0001	Page 2 of 61

TABLE OF CONTENTS

1.	HSE REQUIREMENTS	7
2.	HSE MANAGEMENT	7
3.	PROJECT RISK MANAGEMENT	7
4.	COMPANY ROLES AND RESPONSIBILITIES	8
5.	CONTRACTOR ROLES AND RESPONSIBILITIES	8
6.	HSE PLAN	9
7.	TRAINING	10
8.	HSE POLICIES AND PROCEDURES OF THE COMPANY	11
9.	HSE COMMUNICATION AND MONITORING OF THE CONTRACT HSE REQUIREMENTS..	12
9.1.	MEETINGS AND REGULAR INSPECTION	12
9.2.	HSE STATISTICAL REPORTING AND INDICATORS	12
9.3.	INFORMATION ABOUT INCIDENTS INVESTIGATION	12
9.4.	HSE INSPECTIONS	13
9.5.	CORRECTIVE ACTIONS	13
10.	HEALTH HYGIENE AND WELFARE	13
10.1.	PROVISION OF EMS	13
10.2.	MEDICAL CARE	14
10.3.	LOCAL HEALTHCARE FACILITIES AND EMERGENCY MEDICAL CARE	16
10.4.	MEDICAL STAFF	17
10.5.	MEDICAL EQUIPMENT	17
10.5.1.	MEDICAL SUPPLIES	17
10.5.2.	ANAPHYLAXIS KIT	17
10.5.3.	AMBULANCE	18
10.6.	OBLIGATIONS AND LIABILITIES OF MEDICAL STAFF	18
10.7.	HEAT STRESS	18

	Development and Production Operations Service CONTRACT for Sohrab Oil Field Well pad Construction (3,4,8) Tender No.: SO-004-00082-03	 DanaEnergy
Rev. 00	Document No. SO-082-DTE-LGN-BD-CFT-0001	Page 3 of 61

10.8. SNAKE AND SCORPION BITE MANAGEMENT	19
10.9. ON SITE DRINKING WATER / MEALS & CATERING / SANITARY BLOCKS	19
11. JOURNEY MANAGEMENT, TRANSPORTATION AND DRIVING.....	19
11.1. TRANSPORTATION.....	19
11.2. JOURNEY MANAGEMENT SYSTEM.....	20
11.2.1. TRAVEL MANAGEMENT POLICY	20
11.2.2. ORGANIZATION & RESPONSIBILITIES.....	20
11.3. ROAD SAFETY.....	21
11.3.1. DRIVER STANDARD	21
11.3.2. SPEED LIMITS.....	21
11.3.3. VEHICLE INSPECTION, CARE & MAINTENANCE	21
11.3.4. VEHICLE EMERGENCY EQUIPMENT.....	22
11.3.5. DAILY VEHICLE INSPECTIONS	22
12. LABOR PROTECTION AND SAFE WORK PRACTICES	23
12.1. CONTRACTOR'S PERSONNEL	23
12.2. PERSONAL PROTECTIVE EQUIPMENT (PPE) AND OTHER EQUIPMENT.....	23
12.3. NATURAL (CONNATURAL) HAZARDS.....	23
12.4. EARTH WORKS AND SPECIAL EQUIPMENT	24
12.5. ELECTRICAL EQUIPMENT	25
12.6. HIGH PRESSURE AIR SYSTEMS, PNEUMATIC AND HYDRAULIC SYSTEMS.....	25
12.7. CHEMICALS AND OTHER HAZARDOUS MATERIALS	25
12.8. FUEL.....	26
12.9. WORK AT HEIGHT	27
12.10. FIRE SAFETY	27
12.10.1. FIRE FIGHTING & EMERGENCY EQUIPMENT.....	28
12.10.2. FIRE PREVENTION	28
12.10.3. FIRE PROTECTION/CONTROL.....	29
12.10.4. FLAMMABLE LIQUIDS AND GASES.....	29

	Development and Production Operations Service CONTRACT for Sohrab Oil Field Well pad Construction (3,4,8) Tender No.: SO-004-00082-03	 DanaEnergy
Rev. 00	Document No. SO-082-DTE-LGN-BD-CFT-0001	Page 4 of 61

12.10.5.	FUEL AND OIL TRANSFERS AND REFUELING.....	29
12.10.6.	PORTABLE CYLINDERS CONTAINING COMPRESSED FLAMMABLE GAS	29
12.10.7.	FLAMMABLE/COMBUSTIBLE LIQUIDS STORAGE.....	30
12.10.8.	LIQUEFIED PETROLEUM GASES.....	30
12.11.	HOT WORKS, WELDING, AND FLAME CUTTING OPERATIONS	30
12.11.1.	GENERAL (HOT WORK, WELDING, FLAME CUTTING):	30
12.11.2.	EQUIPMENT (HOT WORK, WELDING, FLAME CUTTING).....	31
12.11.3.	WELDING FUMES AND VENTILATION	32
12.12.	PERMIT TO WORK (PTW)	32
12.13.	LOAD LIFTING	32
12.14.	HOUSEKEEPING:	32
12.15.	EMBANKMENT, EXCAVATION AND TRENCHING	33
12.15.1.	UNDERGROUND HAZARDS:	34
12.15.2.	TOXIC GAS AND LOW OXYGEN HAZARDS OR/AND GAS RELEASE:	34
12.15.3.	VEHICLE TRAFFIC AND FALLING LOADS:.....	34
12.15.4.	STABILITY OF NEARBY STRUCTURES	34
12.15.5.	ESCAPE MEANS FROM TRENCHES	34
12.15.6.	INSPECTIONS	35
12.15.7.	PREVENTION OF CAVE-INS.....	35
12.16.	CONFINED SPACES	35
12.17.	NON-DESTRUCTIVE TESTING (NDT) AND RADIATION PROTECTION.....	35
12.18.	EMERGENCY ACTION PLAN AND RESPONSE.....	36
12.19.	SECURITY	36
12.20.	LOCK-OUT/TAG-OUT (LOTO - ENERGY ISOLATION)	36
12.21.	PIPELINE SAFETY:	37
12.21.1.	DESIGN OF A PIPELINE	37
12.22.	WORK IN PROXIMITY TO EXPOSED ENERGIZED POWER SOURCE AND ELECTRICAL SYSTEM EQUIPMENT	37

	Development and Production Operations Service CONTRACT for Sohrab Oil Field Well pad Construction (3,4,8) Tender No.: SO-004-00082-03	 DanaEnergy
Rev. 00	Document No. SO-082-DTE-LGN-BD-CFT-0001	Page 5 of 61

13.	ENVIRONMENT WASTE MANAGEMENT	38
13.1.	WATER CONSUMPTION AND DISCHARGES TO LAND AND AQUATIC ENVIRONMENT ..	39
13.2.	ATMOSPHERIC EMISSION	39
13.3.	WASTE MANAGEMENT AND REDUCTION.....	40
13.4.	BIODIVERSITY	41
13.5.	SPILLS OF OIL AND FUEL AND LUBRICANTS.....	41
13.6.	ENVIRONMENTAL PROTECTION MEASURES	41
13.6.1.	WATER PROTECTION ZONES:	41
13.6.2.	SOIL LAYER:	42
13.6.3.	NOISE:.....	42
13.6.4.	LIGHTING:	42
13.6.5.	SEPTIC TANK	42
13.6.6.	SEWAGE WATER	42
14.	HSE REQUIREMENTS OF CAMPS AND WORKSHOPS.....	43
14.1.	CAMP STANDARDS.....	43
14.2.	CAMP HYGIENE	43
14.3.	ACCOMMODATIONS	43
14.4.	KITCHEN AREA & FOOD STORAGE	43
14.5.	MESS AREA.....	44
14.6.	CHEMICAL STORAGE	44
14.7.	TOILET, SANITARY FACILITIES & LAUNDRY.....	44
14.8.	ELECTRICAL SYSTEM.....	44
14.9.	VEHICLE MAINTENANCE AREA	45
15.	LIQUIDATED DAMAGES	45
15.1.	LIFE SAVING RULES ENFORCEMENT.....	46
15.2.	DRIVER DISCIPLINARY PROCEDURE.....	49

	Development and Production Operations Service CONTRACT for Sohrab Oil Field Well pad Construction (3,4,8) Tender No.: SO-004-00082-03	 DanaEnergy
Rev. 00	Document No. SO-082-DTE-LGN-BD-CFT-0001	Page 6 of 61

Appendix 1 HSE Reports:	50
Appendix 2: Minimum HSE Manpower and experience for Construction operations not limited to:	52
Appendix 3: Minimum activities, responsibilities and services required by a dedicated HSE CONTRACTOR but not limited to:	53
Appendix 4 Ambulance Checklist.....	55
Appendix 5 Clinic Checklists	58
Table 1 HSE LIQUIDATED DAMAGES	45
Table 2: Some instances of non-compliance including the CONTRACTOR's violation of the provisions/fault and refusal to comply with HSE implementation	48
Attachment 1: NIOC, COMPANY HSE procedures and checklists:	61

	Development and Production Operations Service CONTRACT for Sohrab Oil Field Well pad Construction (3,4,8) Tender No.: SO-004-00082-03	
Rev. 00	Document No. SO-082-DTE-LGN-BD-CFT-0001	Page 7 of 61

1. HSE REQUIREMENTS

- CONTRACTOR shall provide COMPANY with its departmental organization chart and CVs (refer to Appendix 2: Minimum HSE Manpower and experience for Construction operations not limited to:) outlining PERSONNEL competencies for COMPANY approval within Five (5) days from SIGNING of the CONTRACT.
- "CONTRACTOR's HSE Representative" shall pertain to the person who shall carry out all duties related to supervision of the proper implementation of the "HSE MS and HSE Plan " in the coordination and under supervision COMPANY's HSE representative.
- CONTRACTOR'S proposed "HSE Management System" shall be submitted for COMPANY approval within Two (2) weeks after SIGNING DATE of the CONTRACT for COMPANY HSE Manager's approval.
- CONTRACTOR shall implement the "HSE Management System" in accordance with the HSE guidelines, standards, procedures, as well as the use of technical and safe procedures for the WORK set forth in the CONTRACT for the whole CONTRACT duration.
- The cost of fulfilling general HSE requirements with the commitment to supply all consumable and non-consumable items and required manpower shall be included in the CONTRACT price and the COMPANY will not pay any additional cost for the implementation of the HSE process and this shall be seen in the prices quoted for the required WORK.
- CONTRACTOR shall be liable for obtaining all necessary licenses and permits for performing the WORK in accordance with the requirements of the legislative and regulatory acts of the Iran, NIOC and COMPANY.

2. HSE MANAGEMENT

- All WORK(s) performed by the CONTRACTOR under the CONTRACT on the territory of the COMPANY without the involvement of subcontractors shall be carried out under the full control and management of the COMPANY in accordance with the HSE MS requirements and the Islamic Republic of Iran laws, NIOC and COMPANY requirements.
- The HSE MS of the CONTRACTOR shall be subject to approval by the COMPANY prior to mobilization and during the entire period prior to the COMPLETION of WORK with the established frequency.
- In instances where CONTRACTOR is required to provide tools, devices, protective mechanisms and equipment to the PROJECT and COMPANY realizes that such devices or EQUIPMENT are not in proper condition, damaged, or not secured, COMPANY shall inform CONTRACTOR to either remove, replace or repair the said the devices or EQUIPMENT. If after Two (2) days, no action was taken by CONTRACTOR, COMPANY shall take necessary action and the cost shall be charged to CONTRACTOR, likewise; any other losses and fines incurred due to non-compliance shall be charged to CONTRACTOR.
- The COMPANY reserves the right to participate in the evaluation and selection of subcontractors and the COMPANY shall monitor the implementation of their activities under the HSE Plan on a monthly basis.

3. Project Risk management

- CONTRACTOR will provide a detailed Hazardous Area Classification zones, HSE Risk Assessment and JSA/JHA for the Gathering Line, Manifold, Wellhead Facilities and MPP Station (Stage-1) SOW and access roads and/or routes to the PROJECT and well site. It shall be approved by COMPANY.

	Development and Production Operations Service CONTRACT for Sohrab Oil Field Well pad Construction (3,4,8) Tender No.: SO-004-00082-03	 DanaEnergy
Rev. 00	Document No. SO-082-DTE-LGN-BD-CFT-0001	Page 8 of 61

- CONTRACTOR shall be responsible for identifying all HSE risks involved in conducting the activities and the controls to get the risks up to a minimum ALARP (As Low as Reasonably Practicable) level.
- It is CONTRACTOR's responsibility to rectify any unsafe conditions or actions to reduce the potential risks. CONTRACTOR has to take corresponding action in time when any anomalies or inspection reports have been informed by the COMPANY. CONTRACTOR shall take all measures to provide safe working conditions and rectify all hazardous area.
- CONTRACTOR with no cost to COMPANY shall consider the risk of H₂S gas release and oil spillage, hazards, implement risk assessment and Job Safety Analysis for all jobs and provide safety H₂S and related equipment (30 min composite SCBAs, minimum Ten (10) set, portable multi gas (LEL, H₂S, O₂ and CO) detector, minimum Two (02) set, and H₂S Personal detector, minimum Twenty (20) No. on site. All equipment shall be approved by COMPANY and required certificate/s shall be submitted to COMPANY.

4. COMPANY Roles and Responsibilities

- COMPANY will prepare "a set of requirements and procedures for CONTRACTOR HSE Management System" by identifying emergency priorities consistent with the HSE objectives in contracts and attach it as appendices to this Section (see Note 01);
- Note 01: In case the COMPANY HSE requirements and procedures are not available, NIOC relevant guidelines, procedures and/or the related international best practices shall be the guideline.
- COMPANY's HSE representative is responsible for all duties related to monitoring CONTRACTOR's proper implementation of the "HSE Management Requirements and Procedures.";
- Prior to CONTRACTOR's commencement of the WORK including mobilization activities approval of CONTRACTOR HSE Plan by COMPANY shall be obtained;
- COMPANY shall evaluate CONTRACTOR and its PERSONNEL in terms of having the required skills and competencies;
- In consortia and partnerships, the extent of obligations and responsibilities of CONTRACTOR's and consultants shall be determined and sharing the HSE responsibilities among them is avoided;
- The performance or supervision of the "HSE management requirements and procedures" to the qualified and approved subcontractors could be authorized in coordination with COMPANY;

5. CONTRACTOR Roles and Responsibilities

- CONTRACTOR HSE management system shall be in accordance with "COMPANY HSE management requirements and procedures";
- CONTRACTOR shall establish a waste management plan, HSE training plan, health management plan and Emergency Response Plan (ERP) in compliance with COMPANY policy and requirements and approval of such document shall be obtained from COMPANY;
- CONTRACTOR shall ensure the provision and allocation of funds and resources for the implementation of the "HSE management requirements and procedures";
- Before the commencement of WORK, CONTRACTOR shall ensure that the technical documents and administrative procedures are in line with the "COMPANY's HSE management requirements and procedures";
- CONTRACTOR is obliged to comply with COMPANY's procedures, instructions, and guidelines for all types of emergency cases (see Note 01);
- CONTRACTOR is solely responsible against any harm and damage occurred to PROJECT-related people, environment and properties, therefore, the relevant cost and impact caused by such non-compliance of HSE management requirements and procedures shall be borne solely by CONTRACTOR;
- CONTRACTOR shall take the necessary immediate and remedial actions regarding risk management, incident control, occupational diseases, and prevention of equipment and environmental damages;

	Development and Production Operations Service CONTRACT for Sohrab Oil Field Well pad Construction (3,4,8) Tender No.: SO-004-00082-03	 DanaEnergy
Rev. 00	Document No. SO-082-DTE-LGN-BD-CFT-0001	Page 9 of 61

- CONTRACTOR is required to completely understand all COMPANY's HSE instructions and guidelines regarding the full implementation of the "COMPANY of HSE Management requirements and procedures" and develop the necessary mechanisms to apply these instructions and guidelines;
- CONTRACTOR shall comply with the GOVERNING LAW, governmental rules and regulations regarding HSE, in addition to the regulations, requirements and procedures of the COMPANY;
- CONTRACTOR is required to obtain technical/safety inspection certificate for cranes, forklifts, scissor lifts etc. from authorized third parties approved by COMPANY;
- CONTRACTOR shall make endeavors to engage in saving energy management at the work site;
- CONTRACTOR is obliged to avoid any damage to environmental protected areas and related fauna and flora available in the Project;
- CONTRACTOR shall make necessary coordination with COMPANY HSE representative to communicate with other Project involved parties;
- CONTRACTOR is required to protect the works and services, the NIOC/PEDEC PERSONNEL, COMPANY's PERSONNEL, CONTRACTOR's PERSONNEL, the general public, the Project equipment, installations and the environment;
- CONTRACTOR shall have a Safe Journey Plan in place;
- CONTRACTOR shall have an HSE inspection plan in place and follow it accordingly;
- In case of emergencies during the provision of work and services, if safety of PERSONNEL, Project assets and environment is threatened, CONTRACTOR shall immediately take the necessary measures without direct communication and notice from COMPANY;
- To implement Emergency Response Plan (ERP). CONTRACTOR shall develop the required procedure and provide the required facilities, equipment and services such as Emergency Medical Services (EMS) including First Aid equipment, ambulance (type B Iran Standard 4374) and clinic services, fire truck (8000-liter water and 2000-liter foam AFFF3% and full equipped with firefighting equipment and tools including but not limited to : 4 No, 60 min. SCBAs, minimum 100 meters Industrial fire houses, Firefighting PPE for all crew, foam and water Nozzles, etc.), one water Tanker truck (with minimum capacity of 16000 Liters), with related and standard equipment (according to NFPA,BS and IPS standards) and/or auxiliary trailers, etc. in line with the activities, scope of work and existing hazards. The quantity and quality of provided facilities, equipment and services shall be approved by COMPANY HSE representative;

Note: Fire truck could be provided by CONTRACTOR upon request of COMPANY (Call Off).

6. HSE PLAN

- The HSE Plan shall be developed by the CONTRACTOR with the assistance of the COMPANY and shall include:
- All areas and stages of the WORK, including mobilization, performance of works, demobilization and reclamation of the WORKSITE.
- Measures to reduce risks, including the risks of subcontractors, associated with the performance of the WORK under the CONTRACT.
- Principles of interaction between the CONTRACTOR and the COMPANY, and between the CONTRACTOR and all subcontractors under the CONTRACT.
- The HSE Plan is an integral part of the CONTRACT and CONTRACTOR shall provide its HSE Plan for COMPANY's approval within Fourteen (14) days from CONTRACT's SIGNING DATE.
- Before the start of the WORK, the CONTRACTOR shall familiarize and instruct its own PERSONNEL and the PERSONNEL of the subcontractors to comply with the requirements and with the activities of the HSE Plan throughout the CONTRACT period.

	Development and Production Operations Service CONTRACT for Sohrab Oil Field Well pad Construction (3,4,8) Tender No.: SO-004-00082-03	 DanaEnergy
Rev. 00	Document No. SO-082-DTE-LGN-BD-CFT-0001	Page 10 of 61

7. TRAINING

- CONTRACTOR shall provide a Training Plan and matrix (formally approved by COMPANY) describing the required training for CONTRACT activities (including refresher training courses) and maintain training records for subsurface and surface activities Including not limited to: safety induction, H2S, firefighting, PTW, health and hygiene, environment, first aid, emergency response, working at height, welding and cutting, rigging and slinging, radiation NDT, excavation, electrical safety, mine and UXO awareness, confined space entry, waste management, scaffolding, defensive driving and etc.
- CONTRACTOR shall ensure that CONTRACTOR PERSONNEL are adequately trained in HSE precautions and safe working practices and aware of the work activity hazards by implementing the risk assessment / Job Safety Analysis before they are involved in the Services and that they are competent to undertake their required duties in a safe and efficient manner and understand how to respond to emergency situations such as firefighting, security evacuation.
- CONTRACTOR shall provide training as appropriate, including but not limited to:
 - a. Training class room on site equipped with PC, Laptop, Printer, the chairs, projector, and other requirement for conducting the training courses (etc.);
 - b. Information regarding the method and observations that can be used to detect the presence of a release of a hazardous chemical, gas and etc., and how to recognize and understand labels, SDS interpretation, and safe procedures;
 - c. Physical and health hazard information;
 - d. Measures to protect the worker from harmful exposure, including engineering, safe work practices, emergency procedures, PPE use, and so forth;
- CONTRACTOR is responsible for maintaining and enhancing the HSE awareness of all PERSONNEL including arranging regular toolbox talks, short training courses and emergency drills. It also includes job related training required by law, COMPANY regulations and CONTRACTOR's own HSE policy, and will provide certificates if so required.
- a) HSE Induction
 - CONTRACTOR shall ensure that all new arrivals including visitors to the work site receives a comprehensive HSE Induction briefing immediately upon arrival at the work site and before new arrivals commence work. The record of all inductions would be kept.
- b) Unexploded ordinance (UXO) and mine
 - To prevent any incident due to the presence of mines and UXO, the CONTRACTOR shall:
 - CONTRACTOR shall hold the Mines and UXO awareness training courses for all employee and visitors at WORKSITE.
 - Perform all excavation work in accordance with COMPANY standard.
 - Only in perform the work in designated and cleared areas provided by COMPANY and approved by NIOC for execution of WORK.
 - During road transport, remain on the main roads to avoid any incident.
- c) First Aid

	Development and Production Operations Service CONTRACT for Sohrab Oil Field Well pad Construction (3,4,8) Tender No.: SO-004-00082-03	 DanaEnergy
Rev. 00	Document No. SO-082-DTE-LGN-BD-CFT-0001	Page 11 of 61

- CONTRACTOR will ensure that at least one person for each 25 people at in PROJECT including camp and catering crew shall receive training on, and is in possession of a valid certificate from a recognized first aid course provider. A team of these advanced first aiders will be maintained at site and will undergo regular training and exercise with the Paramedic or/and Doctor. First aid, as a minimum requirement, shall include but not be limited to, the control of bleeding and provision of resuscitation.

d) Fire Fighting

- CONTRACTOR will ensure that a dedicated Fire Response Team is maintained at site with trained and experienced PERSONNEL in Fire Fighting. This team will conduct regular Firefighting exercises. The team leader will also be responsible for ensuring that all crew receive regular instructions in basic firefighting techniques, which shall include at least an actual demonstration, and that inspections are carried out in accordance with manufacturers' requirements. Fire and evacuation drills shall take place within a month of startup and thereafter on a regular basis with emphasis on high-risk areas, camps and storage facilities.

e) Defensive Driving Training

- CONTRACTOR will ensure that all of its drivers and heavy equipment operators undergo a formal course on Defensive Driving by a Third Party for Certification of drivers and heavy equipment's operators' competency prior to mobilization at its own cost.

8. HSE POLICIES AND PROCEDURES OF THE COMPANY

- The CONTRACTOR PERSONNEL involved in the performance of the WORK at the facilities of the COMPANY shall know and comply with the requirements of the HSE standards applicable to the WORKS performed, including those listed below applicable to all types of the WORKS and activities:
 - Health, Safety and Environment Policy of "COMPANY".
 - Alcohol and Drug Policy.
 - Stop Work Policy.
 - Standard for the Health, Safety and Environment Management System.
 - Regulation on operational notification and investigation of HSE incidents.
 - Procedure "Permit to Work and list of hazardous jobs".
 - Methodology of implementing the effective workspace system (5S system) at enterprises and offices of COMPANY.
 - Emergency Response Program.
- The COMPANY shall inform the CONTRACTOR of all additional HSE standards applicable but not listed in this Section, and the CONTRACTOR shall notify the COMPANY within Thirty (30) calendar days of the implementation of the standards or contradictions to the legislative requirements of Iran.
- The CONTRACTOR shall take measures to familiarize itself with the Policies and Standards of the COMPANY specified in this Section,
- The CONTRACTOR's HSE standards and procedures applicable to the WORKS under the CONTRACT shall be agreed with the COMPANY and included in the relevant section of the HSE Plan.
- All buildings and structures used in the performance of the CONTRACT, such as offices, rotational camps, canteens and equipment for drinking water supply, shall be equipped in compliance with the

	Development and Production Operations Service CONTRACT for Sohrab Oil Field Well pad Construction (3,4,8) Tender No.: SO-004-00082-03	 DanaEnergy
Rev. 00	Document No. SO-082-DTE-LGN-BD-CFT-0001	Page 12 of 61

current laws of Iran and the standards of the oil industry, as well as the conditions and the requirements set out in this Section.

- The use of freight containers as office, living and dining rooms is prohibited.
- Smoking is strictly prohibited in all workplaces, whether public, outdoor or indoor.
- The CONTRACTOR is obliged to comply with the requirements of the Travel Management Procedure and Policy of the COMPANY.
- If the activities of the CONTRACTOR will be carried out in the existing divisions or in the case of proximity of the CONTRACTOR's workshop to the existing facilities, it is necessary to obtain a permission to perform the WORKS in accordance with the Laws of Iran and COMPANY and CONTRACTOR's HSE standards.

9. HSE COMMUNICATION AND MONITORING OF THE CONTRACT HSE REQUIREMENTS.

9.1. MEETINGS AND REGULAR INSPECTION

- The top management of the CONTRACTOR shall regularly visit the WORKSITE at least once a month. All visits must be documented (protocols, visit reports, instructions, etc.) by CONTRACTOR.
- The CONTRACTOR shall regularly hold its own HSE meetings at different levels to ensure the exchange of HSE information. COMPANY may decide to participate in the meeting.
- COMPANY HSE REPRESENTATIVE and CONTRACTOR HSE REPRESENTATIVE shall convene joint meetings to review outcomes of the activities under the CONTRACT. This will include an analysis of the HSE activities during the WORKS, performance evaluation, lessons learned and recommendations for upcoming PROJECTS.

9.2. HSE STATISTICAL REPORTING AND INDICATORS

- When performing WORKS or providing services on COMPANY's premises for more than one (1) month, the CONTRACTOR shall keep records and submit the HSE statistical data to the COMPANY on monthly basis, no later than the 2nd day of the following month, using the form specified in HSE Plan (or, prior to HSE Plan approval - in accordance with the form of Attachment 2). The COMPANY reserves the right to make changes to the specified form with the notification to the CONTRACTOR in case of changes in the requirements of the Laws of Iran.
- If the CONTRACTOR or SUBCONTRACTORS have their own residential camps, as well as temporary storage of Municipal Solid Waste (MSW) and Industrial Waste (IW), the CONTRACTOR shall submit a Quarterly Report to the COMPANY regarding the Waste Management of contractors and subcontractors, no later than the 2nd day of the month following the reporting quarter.
- The report on the PERSONNEL diseases (COVID and other diseases) shall be provided daily to the HSE Service of the COMPANY.
- All reports must be submitted in English.
- The CONTRACTOR HSE REPRESENTATIVE shall attend the HSE meetings organized by the COMPANY HSE REPRESENTATIVE regularly (twice a month, unless otherwise specified). Minutes of meeting shall be prepared by CONTRACTOR HSE REPRESENTATIVE and sent to COMPANY within Three (3) days from date of the meeting for approval.

9.3. INFORMATION ABOUT INCIDENTS INVESTIGATION

- CONTRACTOR shall follow the HSE reporting procedures set up by COMPANY in the forms of daily, weekly, monthly, incident, accident or investigation reports.

	Development and Production Operations Service CONTRACT for Sohrab Oil Field Well pad Construction (3,4,8) Tender No.: SO-004-00082-03	 DanaEnergy
Rev. 00	Document No. SO-082-DTE-LGN-BD-CFT-0001	Page 13 of 61

- Occupational fatalities, injuries, illnesses, and near miss incidents shall be reported in accordance with COMPANY policy. Additional reports to regulatory agencies and others may be required.
- CONTRACTOR is responsible for conducting a professional investigation, at no additional costs to COMPANY. They shall promptly inform the COMPANY verbally via Telephone or Mobile within 2 hours of occurrence, and then submit a brief accident report to COMPANY within 24 hours. Detailed investigation report shall be submitted to COMPANY in a format acceptable to the COMPANY (Attachment 3) within three (3) calendar days, outlining the events related to the incident. COMPANY may request a joint investigation with CONTRACTOR if deemed necessary.
- The COMPANY has the right to investigate any of the incidents whenever and wherever it occurs and The CONTRACTOR shall provide all possible assistance and, if necessary, participate in the investigation of such incidents conducted by the COMPANY.
- The CONTRACTOR shall comply with all recommendations arising from the investigation of an incident and ensure that the results of the investigation are fully communicated to the CONTRACTOR'S PERSONNEL and/or the SUBCONTRACTOR, as well as to the COMPANY.

9.4. HSE INSPECTIONS

- The CONTRACTOR shall provide the COMPANY or its authorized persons with unrestricted access to the facilities, equipment, materials, PERSONNEL and records of the CONTRACTOR and subcontractors within the agreed time frame (except when CONTRACTOR is prohibited by law or contractual obligations from disclosing such information) to conduct HSE inspections on the basis of internal regulatory documents of the COMPANY. The CONTRACTOR shall comply with all the agreed recommendations issued based on the results of such inspections within the terms agreed between COMPANY and CONTRACTOR.

9.5. CORRECTIVE ACTIONS

- In case of violation by the CONTRACTOR or subcontractors of the requirements of the CONTRACT, the HSE requirements of the legislation of Iran or the HSE Plan, COMPANY shall provide CONTRACTOR with a written notice and the CONTRACTOR shall take measures to correct violations within the time agreed with COMPANY.
- A written notice of violation shall be signed by CONTRACTOR REPRESENTATIVE or SUBCONTRACTOR authorized in accordance with the HSE Plan.
- The COMPANY has the right to stop the CONTRACTOR'S or subcontractor's WORKS at any time due to violations of the requirements of the CONTRACT, the HSE requirements of the legislation of Iran, NIOC, COMPANY and/or the HSE Plan.
- In the event of repeated violation by the PERSONNEL of CONTRACTOR and subcontractor of the HSE requirements, the COMPANY may require the CONTRACTOR to remove the relevant PERSONNEL from WORKS.
- The COMPANY shall not be responsible for any expenses directly or indirectly related to the actions specified in this clause of the CONTRACT.

10. HEALTH HYGIENE AND WELFARE

10.1. PROVISION OF EMS

- CONTRACTOR is required to provide and maintain a medical service with sufficient space (at least 30 m2) and 24/7 competent medical crews including at least one nurse and one technician and one paramedic. The medical space shall be specified for waiting room and Emergency Medical Services (EMS) room. The EMS equipment includes but not limited to patient bed, required EMS equipment

	Development and Production Operations Service CONTRACT for Sohrab Oil Field Well pad Construction (3,4,8) Tender No.: SO-004-00082-03	 DanaEnergy
Rev. 00	Document No. SO-082-DTE-LGN-BD-CFT-0001	Page 14 of 61

(according to relevant standard), minimum set of medicines, ambulance type B (ISIRI 4374 and/or other relevant standards) with competent driver.

- The CONTRACTOR shall provide accommodations, water, septic and utilization of the sewage water, waste management and medical waste management, fuel, mobile phones, transportation, shaded parking lot for ambulance, stationary & administrative materials and any other utilities for accommodations by its own cost. The CONTRACTOR shall also provide drinking water and food for clinic staff.
- EMS crew, equipment and ambulance competencies and qualifications shall be complying with NIOC, legal requirement and procedure and approved by COMPANY.

10.2. MEDICAL CARE

- The CONTRACTOR shall engage PERSONNEL who have no medical contraindications to the work performed at the facilities of the COMPANY.
- The CONTRACTOR shall arrange and pay for the periodic medical examination of each employee involved in the WORKS under the CONTRACT in the territory of Iran in accordance with the requirements of the current legislation.
- Preliminary and periodic medical examinations of each employee of the CONTRACTOR shall be carried out in accordance with the current Laws of Iran.
- A Medical Examination Report shall be prepared for each employee of CONTRACTOR, in compliance with the laws of Iran. CONTRACTOR shall maintain occupational aptitude statements and the authorized medical staff of the COMPANY has the right to review these documents.
- Any employee of CONTRACTOR who is temporarily disabled for medical reasons shall be relocated from the place of WORK until the working capacity is restored, as certified by a sick leave certificate or a certificate of a licensed medical institution in accordance with the current legislation of Iran. Any expenses incurred in this regard, including transport, necessary medical support, or other actions, shall be charged to the CONTRACTOR and shall not be charged to its employees or to the COMPANY.
- The CONTRACTOR is responsible for providing first aid to its employees its own expense, unless stated otherwise in the CONTRACT.
- The PERSONNEL provided by the CONTRACTOR and the SUBCONTRACTORS shall be physically fit to perform the work, have all the necessary vaccinations applicable to the area in accordance with the national immunization schedule of Iran.
- The CONTRACTOR is obliged to provide medical resources and medical equipment necessary to comply with the existing HSE standards of Iran and the COMPANY, which are specified in the agreed HSE Plan.
- The field development will include the provision of a fully equipped clinic within the permanent camp together with an ambulance (Type B) by the CONTRACTOR. CONTRACTOR clinic, Paramedic, nurse, and ambulance drivers shall be Certified by authorized center and capable of providing first aid line, medical assistance and triage so as to stabilize patients for MEDEVAC (Medical Emergency Evacuation Plan) to a hospital in nearest hospital or other reasonable locations.
- Suitable facilities for quick drenching or flushing of the eyes or body, or both, shall be readily accessible for emergency use where PERSONNEL can be exposed to injurious corrosive materials.

	Development and Production Operations Service CONTRACT for Sohrab Oil Field Well pad Construction (3,4,8) Tender No.: SO-004-00082-03	
Rev. 00	Document No. SO-082-DTE-LGN-BD-CFT-0001	Page 15 of 61

- An individual trained in first aid and Cardiopulmonary Resuscitation (CPR) techniques should be available at the WORKSITE to render aid. The individual(s) should be trained using approved courses.
- A first aid kit shall be maintained and available at the WORKSITE. The kit should contain appropriate materials and should be inspected at frequent intervals and replenished as necessary.
- CONTRACTOR'S medical, equipment, ambulance and medical team qualification shall be approved by COMPANY'S HSE Department.
- CONTRACTOR shall provide ambulance Type B with all related equipment's (Dc Shock/ AED) and accessories.
- CONTRACTOR shall ensure that all its PERSONNEL and/or other PERSONNEL assigned by the CONTRACTOR for the performance of the Work are medically fit and healthy. Any medical disabilities including such disabilities which CONTRACTOR may consider will not adversely influence the person's ability to perform his role in the Work should be reported to COMPANY prior to the start of the Work. CONTRACTOR, if requested by COMPANY, shall provide medical certificates for CONTRACTOR and SUBCONTRACTOR PERSONNEL.
- All CONTRACTOR PERSONNEL are to undergo an annual medical check-up at CONTRACTOR expense, to certify their fitness for duties in harsh environment. Valid medical certificates are to be kept together with the PERSONNEL records for inspection purposes.
- CONTRACTOR shall subject its key PERSONNEL and its SUBCONTRACTOR PERSONNEL to regular medical examination at their cost. Records of such examination shall be made available to COMPANY on request.
- CONTRACTOR shall at no cost to COMPANY be responsible for make an agreement with nearest hospital to the PROJECT, for any emergency cases or reception for medical treatment or hospitalization.
- CONTRACTOR shall at no cost to COMPANY be responsible for providing clinic, medical services, equipment, first aid facilities and hospitalization and suitable insurance coverage for all its PERSONNEL employed on WORKSITE for the performance of the Work by CONTRACTOR and SUBCONTRACTORS. In cases of emergency, COMPANY may make or provide for the necessary emergency arrangements. The relevant cost shall be paid or reimbursed by CONTRACTOR.
- In the event that any of CONTRACTORS' employees are treated or seen by a physician or hospital, whether in an emergency medical clinic or elsewhere, CONTRACTOR shall promptly make payment for such treatment directly to the provider of such treatment.
- In any case, all COMPANY medical facilities/services used by/given to CONTRACTOR shall be on the CONTRACTOR's account.
- Unless otherwise specified in the CONTRACT, CONTRACTOR shall be liable for the provision of emergency medical care services and resources to its PERSONNEL that meet the standards of Iran and COMPANY. Specific measures in this area shall be agreed upon prior to mobilization and documented in the HSE Plan.
- The CONTRACTOR shall ensure that all of its and its subcontractor's employees are medically fit and healthy. The CONTRACTOR will arrange following medical examination for its entire staff at CONTRACTOR's own cost:
 - Blood CP & ESR;

	Development and Production Operations Service CONTRACT for Sohrab Oil Field Well pad Construction (3,4,8) Tender No.: SO-004-00082-03	 DanaEnergy
Rev. 00	Document No. SO-082-DTE-LGN-BD-CFT-0001	Page 16 of 61

- Fastening Blood Sugar;
 - Urine D/R;
 - Stool D/R;
 - Chest x-ray P/A view;
 - VDRL;
 - Serum Creatinine;
 - ECG;
 - Drug Test for Urinary opiates;
 - Drug Test for urinary Cannabinoids.
- In addition to these tests physical examination should also be carried out. The Certificates of Medical Fitness must be kept at Site Clinic with test reports of above-mentioned general tests.
 - In addition to the above general test, CONTRACTOR's and its SUBCONTRACTOR'S drivers and heavy equipment operators will also undergo the following tests:
 - Audiometry Test;
 - Eye Vision Test
 - Drug Test for Urinary opiates;
 - Drug Test for urinary;
 - Cannabinoids.
 - All Food handlers (Cooks, Dishwashers and Waiters etc.) must have a more thorough screening than the general work force, with following additional tests. CONTRACTOR will maintain medical records of the catering staff.
 - Blood analysis: CBC (cells blood count), DLC;
 - Urine analysis: For urinary tract infection and kidney problems;
 - Chest X ray;
 - Stool analysis for (a) parasites, (b) pathological bacteria (c) typhus or typhoid carrier;
 - Tested and then vaccinated for Hepatitis A&B;
 - Vaccination against typhoid disease;
 - Receiving the health card from authorized organization.

10.3. LOCAL HEALTHCARE FACILITIES AND EMERGENCY MEDICAL CARE

- In places where the CONTRACTOR occupies a camp or base in the countryside (or uses the camp or base together with other CONTRACTORS), a first-aid post or clinic that meets the EMS requirements of the CONTRACTOR's SOW in comply with Iran shall be arranged.
- Where the work of the CONTRACTOR is considered to be dangerous, and the place of work is remote, a first-aid post shall be provided at this particular WORKESITE recommended by COMPANY on the basis of the risk assessment made. CONTRACTOR shall at its own expense equip such a first-aid post in accordance with the norms in force in Iran.

	Development and Production Operations Service CONTRACT for Sohrab Oil Field Well pad Construction (3,4,8) Tender No.: SO-004-00082-03	 DanaEnergy
Rev. 00	Document No. SO-082-DTE-LGN-BD-CFT-0001	Page 17 of 61

10.4. MEDICAL STAFF

- If it is provided for by the HSE Plan, the CONTRACTOR shall ensure the availability of qualified medical PERSONNEL. Medical PERSONNEL (one nurse and one technician and one paramedic) must be competent and have appropriate training to aid in case of incidents, accidents and resuscitation. All medical PERSONNEL must be trained and allowed to work in accordance with the standards of Iran.
- CONTRACTOR shall ensure the appointment of Liable Personnel for the provision of first aid in each work shift at each WORKESITE. The person liable for providing medical care should undergo a first aid course, at least including, but not limited to, treatment of bleeding and basic life-support measures.
- CONTRACTOR clinic, paramedic, nurse, and ambulance drivers shall be Certified by authorized center and approved by COMPANY.
- CONTRACTOR shall recruit a qualified Paramedic and nurse to be present in clinic 24 hours a day.
- First aid providers should have free access to first aid equipment.

10.5. MEDICAL EQUIPMENT

10.5.1. MEDICAL SUPPLIES

- Medicines for general consultation and ailments are not included in the above list as various medicines are marketed with a variety of names. Care should be taken that the medicines in the clinic cover all general diseases and that sufficient quantity is available.
- The following broad groups of medicines should always be available in the field clinic:
 - Local Anesthetics;
 - Non-steroidal anti-inflammatory drugs (NSAIDs) – oral and injectable;
 - Opioids Analgesics – oral and injectable;
 - Anti-Allergic drugs – oral and injectable;
 - Anti-biotic – oral and injectable;
 - Anti-fungal – local application / oral;
 - Anti-amoebic;
 - Anti-malarial;
 - Anti-pruritic;
 - Antacids including H-2 receptor antagonists;
 - Antiemetic's;
 - Antispasmodics;
 - Anti-asthmatic drugs – inhalers and injectable;
 - Cardiovascular drugs e.g., Nifedipine;
 - Drugs used in diarrhea including Oral Rehydrating Solution (ORS);
 - Drugs used in eye diseases;
 - Drugs used in ENT diseases;
 - Diuretics.

10.5.2. ANAPHYLAXIS KIT

- Adrenaline (epinephrine) – 3x ampoules of Adrenaline 1mg/ml solution (1:1000 solution)
- Chlorpheniramine (or similar antihistamine) – 2x ampoules of Chlorpheniramine 10mg/ml
- Hydrocortisone (succinate or sodium phosphate) – Dry powder (requires Water for Injection for mixing) or ampoules of solution 100mg/ml. A total dose of 500mg should be available. Or:
 - Dexamethasone injection, 4mg (as sodium phosphate) in 1-ml ampoule;
 - Guedel Airways – Minimum of two of each size;

	Development and Production Operations Service CONTRACT for Sohrab Oil Field Well pad Construction (3,4,8) Tender No.: SO-004-00082-03	 DanaEnergy
Rev. 00	Document No. SO-082-DTE-LGN-BD-CFT-0001	Page 18 of 61

- Hand operated ventilation bag and mask;
 - Appropriate syringes and needles;
 - Intravenous Infusion;
 - Oxygen (Medical quality oxygen and appropriate administration set);
 - Laryngoscope and endotracheal tubes;
 - Other equipment for Cardio-Pulmonary resuscitation should be available.
- The Medical Equipment required for the clinic is listed on the next two pages. However, ECG Machine & Defibrillator should be present and the doctor needs to be trained to use it.

10.5.3. AMBULANCE

- CONTRACTOR shall provide ambulance Type B according to Iran Standard 4374, (prefer the four-wheel drive) vehicle for use as a properly fit-ted out ambulance at site on a 24 hours' basis. (Refer to Appendix 4 Ambulance Checklist);
- Ambulance shall be in good and safe condition ready to use. It should contain but not limited to:
 - DC Shock/AED;
 - Oxygen cylinder with face mask;
 - Stretcher;
 - Communication facilities;
 - Emergency Light;
 - Rotating flashing beacon lights;
 - Portable suction machine.
- Emergency kit containing items mentioned above. The kit needs to be placed in the clinic because of the controlled temperature, and will be kept in the ambulance in case of emergency.
- Ambulance shall not use for any other reasons except for emergency situation.

10.6. OBLIGATIONS AND LIABILITIES OF MEDICAL STAFF

- The CONTRACTOR's medical staff shall be liable for hygiene control at all camp facilities, including the quality of drinking water, quality of food, hygiene of living areas, removal and disposal of household waste, control of sewerage and pest control.

10.7. HEAT STRESS

- CONTRACTORS are advised to train his personnel about heat stress hazard, and shall provide Heat Management Guidelines. The necessary precautions shall be provided by CONTRACTOR.
- CONTRACTOR shall develop and Heat Management Program.
- The following practices and controls can be used to minimize the effect of high temperatures on human body:
 - Provide cool (shaded) areas for rest and recovery.
 - Ensure adequate supply of cool water at the work place
 - Ensure that employees take fluids at least every hour.
 - If workers' diet is insufficient in salt or an individual is susceptible to heat strain, the water can be salted. People on salt restricted diet (e.g. high blood pressure) should consult the doctor before taking additional salt.

	Development and Production Operations Service CONTRACT for Sohrab Oil Field Well pad Construction (3,4,8) Tender No.: SO-004-00082-03	 DanaEnergy
Rev. 00	Document No. SO-082-DTE-LGN-BD-CFT-0001	Page 19 of 61

10.8. SNAKE AND SCORPION BITE MANAGEMENT

- CONTRACTORS are advised to train his PERSONNEL about snake bite hazard and shall take necessary emergency actions and precaution on site.

10.9. ON SITE DRINKING WATER / MEALS & CATERING / SANITARY BLOCKS

- CONTRACTOR shall ensure that adequate cool, clean and sanitary drinking water and ice is available on site for its employees and subcontractors.
- Drinking water shall be controlled through bacteriological and chemical analysis according to ISIRI 1053 and the results shall be submitted to COMPANY for review.
- Meals shall not be served at working places, but in specially designed area, which shall be kept, clean and tidy.
- CONTRACTOR shall be made available sanitary blocks / Porto cabins including toilets, hand washing basins, hand cleansers and water etc. In sufficient quantities and at adequate work locations. Sanitary blocks shall be kept clean, tidy and in service all the time. They shall be equipped to non-absorbable septic tanks easily dischargeable.

11. JOURNEY MANAGEMENT, Transportation and DRIVING

11.1. Transportation

- CONTRACTOR Traffic Management Plan, Transportation plan, Journey plan and policy shall be developed and shall be forwarded to COMPANY for review and approval.
- It is COMPANY policy, in line with HSE commitment, to pursue the goal of no harm to people, and to prevent all road accidents that might arise as a consequence of activities. This policy applies to all COMPANY's staff, CONTRACTORS and vehicles engaged in the business of the CONTRACT.
- In this regard, CONTRACTOR shall:
 - At its own cost, shall ensure that CONTRACTOR's drivers have proper valid driving license and health certificate.
 - Ensure that all drivers are able to demonstrate his relevant authorized driving and operating license, specific license for each individual vehicle if any.
 - Actively promote the awareness of and motivation for safe driving techniques in all circumstances.
 - Test professional drivers on a yearly basis for medical fitness and eyesight.
 - Not tolerate any violation of the substance abuse policy.
 - Ensure that all vehicles are suitable for their intended use, are adequately maintained and checked, and that seat belts are correctly installed.
 - Require that all drivers and passengers traveling by car or other light vehicle on COMPANY business wear the seat belts.
 - Meet COMPANY traffic policy, all drivers related legislative requirements and rules in worksite and outside.
 - Ensure to hold regular Defensive Driving training course for drivers.
 - Ensure that any load being transported to the site is secure and meets the COMPANY HSE policy.
 - Deliver all vehicle and driver document (Original Insurance, driving license, etc.) to COMPANY HSE REPRESENTATIVE when requested.

	Development and Production Operations Service CONTRACT for Sohrab Oil Field Well pad Construction (3,4,8) Tender No.: SO-004-00082-03	 DanaEnergy
Rev. 00	Document No. SO-082-DTE-LGN-BD-CFT-0001	Page 20 of 61

- Driving the vehicles without driving license is prohibited and COMPANY has right to stop the violated driver and remove him from PROJECT. It is CONTRACTOR responsibility to take immediate action in this regard.
- Whenever the CONTRACTOR's PERSONNEL or of its AFFILIATES, AGENTS or of its subcontractors are employed working in the WORKSITE or are traveling to or from WORKSITE, then the CONTRACTOR shall ensure that they shall comply with both the COMPANY's safety regulations currently in force and the safety provisions contained in the CONTRACT.
- Note: all CONTRACTOR vehicles trucks, mechanical shovels, loaders, water tankers trucks, Backhoe, compactors and any other equipment shall have valid inspection certificates from legal authority and approved 3rd party.
- Any violation in driving that result to any accident shall be subjected to LIQUIDATED DAMAGES to CONTRACTOR by COMPANY and will be imposed on the driver and CONTRACTOR.
- Whenever the personnel of the CONTRACTOR or of its Affiliates, agents or of its SUBCONTRACTORS are employed working in the CONTRACT Area or are traveling to or from CONTRACT Area, then the CONTRACTOR shall ensure that they shall comply with both the COMPANY's safety regulations currently in force and the safety provisions contained in the CONTRACT.

11.2. Journey Management System

- CONTRACTOR is required to establish and maintain a Journey Management System to ensure safe travel of all personnel and equipment.
- The components of the journey management system are:
 - A. Travel Management Policy;
 - B. Organization and Responsibilities;
 - C. Planning;
 - D. Risk Assessment;
 - E. Driver Standards;
 - F. Vehicle standards;
 - G. Implementation;
 - H. Monitoring.

11.2.1. Travel Management Policy

- The travel management policy would define the CONTRACTOR's commitment to safe travel and ways and means to achieve this objective.
- The Travel Management Policy is the starting point for achieving safe travel and has the objective of:
 - 1) Reducing the number of travel-related accidents
 - 2) Minimizing the amount of risk exposure from traveling
 - 3) Specifying the organization for travel management
 - 4) Establishing criteria for the selection and use of different modes of transport
 - 5) Establishing criteria for persons in charge of different modes of transport
 - 6) Establishing safe working procedures for traveling
- CONTRACTOR shall prepare a detailed journey management system after award of contract for approval by COMPANY. The system will conform to all current COMPANY procedures.

11.2.2. Organization & Responsibilities

	Development and Production Operations Service CONTRACT for Sohrab Oil Field Well pad Construction (3,4,8) Tender No.: SO-004-00082-03	 DanaEnergy
Rev. 00	Document No. SO-082-DTE-LGN-BD-CFT-0001	Page 21 of 61

- Include an Organization chart showing relationships of those with responsibilities for specific aspects of travel management.
- Outline responsibilities of posts shown on the organization chart.

11.3. ROAD SAFETY

- All vehicles engaged by CONTRACTOR and SUBCONTRACTOR for the performance of works under the CONTRACT shall comply with Iran Laws, Vehicle Standards, and "Technical Requirements for Vehicles".
- CONTRACTOR shall ensure that the drivers (both its own and the SUBCONTRACTOR's drivers) inform and comply with the established speed limits on the territory of production facilities in accordance with the requirements of the legislation of Iran and the COMPANY requirements.
- CONTRACTOR is required to obtain and submit valid health certificates for drivers and workers working in dining rooms, kitchens etc. to COMPANY HSE representative.
- CONTRACTOR shall follow the COMPANY driving standards, as a minimum, comply with Local driving legislation and other legislation on driver and vehicle fitness. In addition to the appropriate type of driving license, CONTRACTOR and SUBCONTRACTOR professional and non-professional drivers shall meet specific criteria on medical fitness, driving knowledge, driving skills and actual road driving behavior. Drivers shall follow specified speed limits, generally lower than legally allowed speed limits.

11.3.1. DRIVER STANDARD

- All drivers shall be in possession of valid driving licenses and health certificates for the appropriate category of vehicle.
- CONTRACTOR will ensure that all of its and its SUBCONTRACTOR's drivers and heavy equipment operators undergo a formal course on Defensive Driving by a Third Party for Certification of drivers' competency prior to mobilization at its own cost.

11.3.2. SPEED LIMITS

- Speed limits set for premises and road systems should be seen to be enforced by line management.
- Speed limits where defined shall be prominently displayed in all vehicles.
- Driving speeds should be further reduced when the visibility is reduced by dust, weather conditions, and time of the day and when driving on wet or muddy road surfaces.
- Speed limiting rules for vehicles on public roads should be set with caution. Enforcing compliance with a limit, which is significantly lower than the limits set by traffic authorities or lower than local norms may increase vehicle hazards due to overtaking.
- GPS system may need to be installed on the vehicles.

11.3.3. VEHICLE INSPECTION, CARE & MAINTENANCE

- All CONTRACTOR and SUBCONTRACTOR vehicles shall be fit for purpose, inspected and confirmed to be in safe working order. All vehicles operated by CONTRACTOR and SUBCONTRACTOR shall meet the COMPANY mandatory requirements that include regular and documented maintenance.
- Care of the vehicle is the responsibility of the CONTRACTOR and SUBCONTRACTOR drivers and includes:

	Development and Production Operations Service CONTRACT for Sohrab Oil Field Well pad Construction (3,4,8) Tender No.: SO-004-00082-03	 DanaEnergy
Rev. 00	Document No. SO-082-DTE-LGN-BD-CFT-0001	Page 22 of 61

- a) Conducting daily inspections of the vehicle on the basis of checklists (tires, fluids, brakes, batteries, lights, etc.) where required;
- b) Ensuring defects that have an immediate effect on safety are reported and that they have been repaired before the vehicle is put back into operation;
- c) Ensuring that a vehicle is sent for Preventive Maintenance as per schedule;
- d) In order to ensure that proper levels of safety are maintained, all vehicles will be subject to regular road worthiness inspections and scheduled maintenance, the frequency should be determined on the basis of local regulations, manufacturer's recommendations, vehicle age, distances traveled and operating conditions;
- e) An effective maintenance program includes but is not limited to:
- f) Pre-use inspections;
- g) Setting of appropriate maintenance standards and criteria for verification;
- h) Schedules for inspection, maintenance and testing;
- i) Check lists to include all safety related items;
- j) Appropriate and reliable working maintenance facilities;
- k) Adequate supply of spare parts;
- l) Roadworthiness tests following damage repairs;
- m) Operating Life of Vehicle & Certification;
- n) All vehicles shall be maintained on standards provided by the manufactures;
- o) Records will be maintained which should be available for verification and audit by COMPANYMY.

11.3.4. VEHICLE EMERGENCY EQUIPMENT

- The following emergency equipment shall be installed and securely fixed, when appropriate, on Heavy Vehicles:
 - a) An in cab fire extinguisher with a capacity of 4 kg. The fire extinguisher shall be securely mounted on a bracket and located so that it is easily accessible in an emergency without becoming a hazard in case of an accident;
 - b) Be fitted with an in external fire extinguisher of a type that is compatible with the load the Vehicle is carrying;
 - c) First aid kit and flashlight/torch;
 - d) Two disabled Vehicle markers (e.g. warning triangle);
 - e) Carry a hi-visibility jacket for the Driver to be used in case of emergency stops;
 - f) Sufficient drinking water for all occupants in the vehicle.

11.3.5. Daily Vehicle Inspections

CONTRACTOR and SUBCONTRACTOR drivers are responsible for conducting pre-trip inspections. Where established by risk assessment by line manager and post trip inspections of the vehicles shall also be required by drivers. The drivers are supposed to fill the pre-use safety checklist

	Development and Production Operations Service CONTRACT for Sohrab Oil Field Well pad Construction (3,4,8) Tender No.: SO-004-00082-03	 DanaEnergy
Rev. 00	Document No. SO-082-DTE-LGN-BD-CFT-0001	Page 23 of 61

12. LABOR PROTECTION AND SAFE WORK PRACTICES

12.1. CONTRACTOR'S PERSONNEL

- The CONTRACTOR shall provide the COMPANY with an experienced and qualified specialist as CONTRACTOR REPRESENTATIVE.
- The CONTRACTOR is obliged to inform in writing COMPANY REPRESENTATIVE of the minimum number of qualified human resources and HSE organizational structure to implement the HSE MS requirements and procedures of the CONTRACTOR, set out in this SECTION, after signing the CONTRACT and before the start of WORKS.
- The adequacy of the organization and the competence of the CONTRACTOR's HSE PERSONNEL shall be approved by COMPANY REPRESENTATIVE before the start of WORKS.
- The CONTRACTOR shall provide only trained and qualified PERSONNEL, including the SUBCONTRACTOR's PERSONNEL, to perform the works.
- The CONTRACTOR shall familiarize the PERSONNEL with the HSE requirements of the COMPANY prior to mobilization under the CONTRACT. CONTRACTOR shall regularly update the lists of employees who have undergone mandatory HSE training and provide them to the COMPANY upon request.
- The CONTRACTOR shall draw up documentary evidence of the completion of HSE training or advanced training for each employee.
- The CONTRACTOR's PERSONNEL and the SUBCONTRACTOR at the facilities shall meet the requirements of Iran and COMPANY in terms of competence, certification and qualification.

All Safe practices shall be followed in accordance with NIOC and COMPANY HSE regulations and procedures including but not limited to:

12.2. PERSONAL PROTECTIVE EQUIPMENT (PPE) AND OTHER EQUIPMENT

- CONTRACTOR shall ensure the use of serviceable Personal Protective Equipment (PPE) by its own PERSONNEL and the SUBCONTRACTOR's PERSONNEL, in accordance with the requirements of Iran. The quantity and quality of PPE shall be approved by COMPANY HSE representative;
- CONTRACTOR shall provide its own PERSONNEL and the SUBCONTRACTOR's PERSONNEL with overalls, personal protective equipment and other equipment necessary for the safe performance of works during the entire period of validity of the CONTRACT.
- All CONTRACTOR's PERSONNEL, SUBCONTRACTORS and employees with daily wages shall be provided with PPE and equipment prior to the start of WORKS.
- PPE shall be uniform and appropriate to the environmental conditions. It shall contain the name of CONTRACTOR or SUBCONTRACTOR and the name of an employee.

12.3. NATURAL (CONNATURAL) HAZARDS

- An appropriate assessment and identification of natural hazards should be given, and therefore, measures to control effectively the situation and eliminate the consequences should be taken in terms of the following factors:
 - Types of work that can be performed in case of bad weather;
 - Weather conditions (sun, rain, fog, thunderstorm, hail, wind, heat);
 - Secondary manifestations of weather conditions (flood, landslide, static electricity);
 - Wildlife (snakes, scorpions, spiders, other poisonous representatives of wildlife, aggressive animals);

	Development and Production Operations Service CONTRACT for Sohrab Oil Field Well pad Construction (3,4,8) Tender No.: SO-004-00082-03	 DanaEnergy
Rev. 00	Document No. SO-082-DTE-LGN-BD-CFT-0001	Page 24 of 61

- Flora (poisonous, penetrating, blocking).
- on daily basis.

12.4. EARTH WORKS AND SPECIAL EQUIPMENT

- Before starting to work with track-type vehicles, all operators must undergo training, obtain qualifications and pass an exam for admission to work with equipment of this category in accordance with the legislation of Iran.
- Each track-type vehicle shall be equipped with the tools ensuring safe work performance, namely:
 - Protective canopy overhead;
 - Automatic reverse horn with intermittent audible alarm;
 - Horn, which overlaps the noise of a working vehicle;
 - Convex rearview mirror;
 - Functioning parking brakes;
 - Lock on the gearbox switch;
 - Means of protecting the driver's hearing from the noise emitted by equipment;
 - Fire extinguisher installed in vehicles;
 - An operator and assistants must wear helmets, special safety shoes and light-reflecting vests.
- CONTRACTOR shall spray water on the roads to prevent of dust creation and low visibility.
- All excavation WORKS shall be performed only with the relevant Work Permit or Permit to perform the works. In addition, the following requirements must be met:
 - A. Provision of warning signs indicating the excavation works being performed. These signs should be:
 - In English and Persian;
 - With colorful graphics;
 - Installed in places that meet the requirements of the HSE REPRESENTATIVE of the COMPANY;
 - B. It is necessary that all operators of equipment have knowledge of hazards, for example, pits and slopes, which are indicated, for example, using flags or stakes;
 - C. It is necessary that all equipment works in a safe mode under the control of qualified operators and supervisors. Under no circumstances an employee may start up the equipment without having the relevant document on professional training and admission to work.
- People should not work or walk near the edges of a trench and pit. Temporary bridges should be arranged over each trench. Such bridges must be at least 600 mm wide, of sufficient length, and also equipped with handrails, at least on one side.
- All pits and trenches (except for main oil and gas pipelines at the construction stage) shall be fenced with hard barrier on all sides and provided with warning signs and notices. Where areas with excavated soil should remain open in the dark, it is necessary to provide a sufficient number of signal lamps installed in key places.
- Near working equipment and machinery (for example, a bucket excavator, a ditch digger, a rock crusher, a jackhammer, etc.) or in places of excavated soil (holes), no one should be closer than 5 m from the working excavation equipment in the recess or closer to 3 m from the operating equipment above. Where manual grading is required at a distance of less than 5 m from the operating machine, the machine should be stopped until the completion of manual work.

	Development and Production Operations Service CONTRACT for Sohrab Oil Field Well pad Construction (3,4,8) Tender No.: SO-004-00082-03	 DanaEnergy
Rev. 00	Document No. SO-082-DTE-LGN-BD-CFT-0001	Page 25 of 61

- All exhaust gases generated by the equipment must be discharged away from the place of excavation works in order to avoid the accumulation of toxic gases in the holes.
- In those holes where oxygen may be difficult to access, the CONTRACTOR or SUBCONTRACTOR shall measure the gas-air environment with its own specialized instrument to determine the oxygen content and, if necessary, install appropriate fans.

12.5. ELECTRICAL EQUIPMENT

- Personnel with appropriate professional training and qualifications in electrical safety in accordance with the requirements of the legislation of Iran and COMPANY may be appointed liable for electrical safety during the work.
- Stationary electrical equipment can be installed only by highly qualified electricians.
- All stationary electrical equipment shall be:
 - Protected by a circuit breaker in case of overloads and poor grounding;
 - Equipped with insulating switches that open both the phase and the neutral conductor.
- All electrical equipment, except for hand tools with double insulation, must be provided with a ground wire.
- Portable electrical equipment should be plugged into sockets with the appropriate nominal value.
- Portable electrical equipment should be disconnected from the power source when not in use.
- All flexible cables must be in good technical condition and protected from mechanical damage.
- The use of twists, incl. insulated ones to connect cables and wires is unacceptable.

12.6. HIGH PRESSURE AIR SYSTEMS, PNEUMATIC AND HYDRAULIC SYSTEMS

- Actions shall be taken to ensure the following:
 - competent staff;
 - allotted territory with warning signs;
 - fan belts, flexible hoses and pulleys with protection;
 - inspection and maintenance programs;
 - proper position, design and operation of safety valves/devices and their periodic testing;
 - use of disconnecting devices and emergency protection devices;
 - position of the bypass manifolds - leave the drain valves open.

12.7. CHEMICALS AND OTHER HAZARDOUS MATERIALS

- General information:
- The CONTRACTOR using chemicals (reagents, etc.) during the performance of WORKS under the CONTRACT shall keep records of stored and used chemicals. Packaging of chemicals shall be airtight and contain information about the substance. Storage of chemicals should be organized in accordance with safety requirements, access to the store should be limited.
- The CONTRACTOR's PERSONNEL working with chemicals shall undergo appropriate training. The action plan in the event of an incident with chemicals shall be located directly at the facility or in the area of the performance of WORKS/ provision of SERVICES under the CONTRACT.
- The CONTRACTOR shall have a system of procedures in force regarding how to handle chemicals and other hazardous substances, namely:

	Development and Production Operations Service CONTRACT for Sohrab Oil Field Well pad Construction (3,4,8) Tender No.: SO-004-00082-03	 DanaEnergy
Rev. 00	Document No. SO-082-DTE-LGN-BD-CFT-0001	Page 26 of 61

- selection, storage, handling and disposal of chemicals
- ability to cope with a chemical spill.
- The CONTRACTOR shall have accurate and updated inventory records of all products requiring material safety data sheets.
- Chemicals storage procedure:
 - Chemicals must be clearly labeled and stored in specially designated safe places.
 - Flammable and highly flammable substances should be stored in a separate place.
 - Personnel handling chemicals must wear personal protective equipment (PPE) as specified in the material safety specifications.
 - Spill response kits should be kept at hand in the places where the relevant work is carried out.
 - Sufficient ventilation.
 - Availability of a fire extinguisher.
 - Material safety data sheets.
- Material Safety Data Sheets for chemicals shall be:
 - Easily accessible on site.
 - Issued to the medical staff of the COMPANY and CONTRACTOR in case of any accidents related to the use of chemicals.
 - Supervisors should have knowledge and experience in handling hazardous materials.
- Material Safety Data Sheets shall contain data on:
 - labeling;
 - work experience;
 - separate storage;
 - personal protective equipment (PPE).
- EMERGENCY EYE OR BODY WASH STATIONS:
- CONTRACTOR shall be providing eyewash and shower equipment for emergency cases Where the eyes or body of PERSONNEL may be exposed to injurious materials according to Project risk assessment.

12.8. FUEL

- The fuel storage area shall:
 - be specially designated for this purpose;
 - be isolated from other dangerous places and sources of open fire;
 - have a bunded area containing at least 50% of the tank contents;
 - have a sealed surface (concrete, insulating materials, etc.);
 - be equipped with highly visible warning signs;
 - be equipped with appropriate fire extinguishing equipment, which should be located within 15 meters from the pumps or a transfer point.
- Fuel transfer:
 - only special road tankers shall be used for this purpose;
 - road tankers must be properly grounded in the process of fuel transfer;
 - mandatory use of appropriate PPE;
 - a trained and experienced worker who is authorized to work with fuel.
 - The place of filling into portable containers shall exclude the ingress of fuel on the ground.

	Development and Production Operations Service CONTRACT for Sohrab Oil Field Well pad Construction (3,4,8) Tender No.: SO-004-00082-03	
Rev. 00	Document No. SO-082-DTE-LGN-BD-CFT-0001	Page 27 of 61

12.9. WORK AT HEIGHT

- Work at height shall include work in which an employee is above 1.5 m from the floor, slab, working floor, and scaffolding must be arranged for its performance.
- Climbing work shall include work in which an employee is at a height of more than 5 m from the floor, slab, working floor.
- When carrying out works at height and climbing work, employees of the CONTRACTOR or SUBCONTRACTOR shall use safety systems in accordance with the requirements of the legislation of Iran.
- Safety harnesses shall be used as a harness in safety systems. The use of strapless safety harnesses is prohibited.
- The connecting subsystem of the safety system shall include a shock absorber or a device that functionally replaces it. Connecting subsystem can be made of slings, self-retracting safety devices or guided type safety devices on flexible or rigid anchor lines.
- Climbing works are allowed for employees not younger than 18 years old and not older than 60 years old, who have undergone a medical examination for fitness for climbing work, trained in the rules of safe performance of climbing works, having the necessary training and practical skills for their performance, have undergone special instructions at the workplace before each work having the appropriate certificate of admission to climbing works in accordance with the requirements of the legislation of Iran.
- If there are electrical and other existing communications in the area of work at height, the work shall be allowed according to the work permit issued or agreed by the organization in charge of these communications.
- Works at height of up to 5 m shall be allowed for employees without special training, but who have undergone a medical examination for fitness to work at height in accordance with the requirements of the legislation of Iran.
- Work at height and climbing work shall be carried out according to the Work Execution Plan (WEP) with mandatory briefing at the workplace with an explanation of:
 - techniques for safe work at height;
 - procedure for approaching the workplace;
 - state of the workplace;
 - nature and safe methods of performing the upcoming work;
 - procedure for using safety devices;
 - manner and place of installation of lifting equipment, etc.;
 - measures to prevent falls from a height, methods of safe passage from one workplace to another;
 - measures to ensure safety during installation in the design position or removal of structures, units, parts, etc.;
 - ensuring the factors of the working environment (illumination, temperature, humidity, wind speed, atmospheric precipitation, noise, vibration, etc.) that are acceptable to employees;
 - condition of scaffolding, platforms, ladders, fences, safety ropes, etc.;
 - need for personal protective equipment - helmets, safety harness, stepladder safety devices, catchers with a vertical rope, etc.

12.10. FIRE SAFETY

- CONTRACTOR shall implement fire precaution procedure including, but not limited to, Camp, vehicles, electrical equipment and generators, welding and cutting devices and post weld heat treatment activities and etc.
- The CONTRACTOR shall be responsible at its own cost to provide, not limited to, all fire

	Development and Production Operations Service CONTRACT for Sohrab Oil Field Well pad Construction (3,4,8) Tender No.: SO-004-00082-03	 DanaEnergy
Rev. 00	Document No. SO-082-DTE-LGN-BD-CFT-0001	Page 28 of 61

extinguishing equipment, fire blanket, flashback arrestor, and fire truck and back up water tanker with related and standard equipment mentioned in 10.12.1.

12.10.1. FIRE FIGHTING & EMERGENCY EQUIPMENT

- CONTRACTOR shall provide adequate Emergency firefighting services including: provide and maintain a foamatic fire truck with require equipment and accessories such as roof top monitor, hose reel (6000 to 8000-liter water and 2000-liter foam AFFF3% and full equipped with firefighting equipment and tools including but not limited to : 4 No, 60 min. SCBAs, minimum 100 meters Industrial fire houses, Firefighting PPE for all crew, foam and water Nozzles, etc. one water Tanker truck (with minimum capacity of 16000 Liters), with related and standard equipment (according to NFPA,BS and IPS standards) and/or auxiliary trailers, etc. and other safety equipment including but not limited to: Scape mask, Personal H2S Detector and etc., in accordance with CONTRACTOR's SOW to handle emergencies. These items should conform to the following minimum COMPANY standards and not limited to:
 1. All items should conform to IPS, ISO, NFPA or equivalent standards;
 2. The equipment is to be maintained in a professional manner as dictated by legal and industry standards;
 3. An up-to-date record of manufacture, testing and maintenance of all equipment is to be maintained;

12.10.2. FIRE PREVENTION

- A fire risk assessment shall be conducted in accordance with COMPANY procedures. The risk assessment shall be reviewed if the fire risks changes. The fire risk assessment may include potential fuel, sources of combustible fluids or vapors, and ignition sources. Results of the risk assessment shall be communicated to the employees and implemented as applicable.
- Combustible and flammable materials shall be stored in accordance with COMPANY procedures and NFPA 30 on the proper storage of combustible and flammable materials.
- CONTRACTOR shall ensure that, discarded oily rags and combustible waste should be stored in metal containers with the covers kept in place.
- Metal or other conductive material containers should be used in handling, storing, or transporting flammable liquids. Metal parts on plastic containers used in such service should be bonded to the fill connection. (According to NFPA 77 and API 2003).
- Smoking is forbidden and shall be permitted only in designated areas approved by COMPANY.
- Only explosion proof and intrinsically safe heaters shall be permitted on or near the wells and process area, substructure, pits, or cellar (according to API 500 or API 505 for guidance on electrical area classification). The safety features of these heaters shall not be altered.
- Stoves and heaters (without naked heating elements) shall only be used in accordance with the manufacturer's recommendations to prevent buildup of carbon monoxide.
- The handling, maintenance, storage, transportation, usage, and disposal of batteries should follow manufacturer recommendations.
- Equipment, cellars, ground areas around and adjacent to the facility should be kept free from oil and gas accumulations that might create or aggravate fire hazards.
- Appropriate and adequate number of fire extinguishers shall be provided to all the facilities and activities.
- Locations of such equipment must be clearly marked and they should be readily accessible to all persons;

	Development and Production Operations Service CONTRACT for Sohrab Oil Field Well pad Construction (3,4,8) Tender No.: SO-004-00082-03	 DanaEnergy
Rev. 00	Document No. SO-082-DTE-LGN-BD-CFT-0001	Page 29 of 61

- Color codes should be used to identify different types of fire extinguishers;
- All persons shall have the basic knowledge of how to operate the equipment, and the procedures to be followed in the event of fire;
- Manual or electrical with backup battery operated Emergency Alarm should be installed at camp sites;
- Muster points/ Safe Briefing Areas should be designated;

12.10.3. FIRE PROTECTION/CONTROL

- CONTRACTOR shall ensure that, proper fire extinguishing equipment and machinery including fire truck, Fire chief vehicle shall be available, suitably located, readily accessible, and plainly labeled as to their type and method of operation.
- CONTRACTOR shall ensure that, all crew members shall be familiar with the location of fire extinguishing equipment and shall be trained in the use of such equipment, application, and associated hazards, in accordance with COMPANY policy.
- Fire extinguishing equipment shall not be tampered with and shall only be used for fire protection, firefighting purposes, and servicing.
- Fire extinguishing equipment shall be periodically inspected and maintained in operating condition. A record of the most recent equipment inspection shall be maintained.

12.10.4. FLAMMABLE LIQUIDS AND GASES

- Containers
 - Hand portable containers for storing flammable liquids or gases should be underwriters' laboratories (UL) or factory mutual (FM) approved, or equivalent.
 - Tanks, drums, and other containers containing flammable liquids or gases should be properly labeled to denote their contents and certified by approved 3rd party.

12.10.5. FUEL AND OIL TRANSFERS AND REFUELING

- A risk assessment should be performed prior to refueling and transfer operations. The risk assessment may include, but is not limited to:
 - Engines running during refueling,
 - Grounding and bonding procedures,
 - Simultaneous operations,
 - Environmental conditions and concerns, and
 - Potential ignition sources.
- Fuel and oil transfer procedures should be established and followed.
- One person should be designated to gauge or monitor tanks (e.g. fuel, mud, etc.) while they are being filled to prevent overfill and spillage.
- Above ground storage tanks and equipment being refueled shall be grounded. Portable containers should be bonded back to the fuel tank during transfer operations.

12.10.6. PORTABLE CYLINDERS CONTAINING COMPRESSED FLAMMABLE GAS

- Portable cylinders that are in use or in storage shall:
 - a) Be secured to prevent them from falling or being knocked over,
 - b) Be transported, stored and used in an appropriate position,
 - c) Use valve protective caps (if designed for) except when being filled or connected for use,

	Development and Production Operations Service CONTRACT for Sohrab Oil Field Well pad Construction (3,4,8) Tender No.: SO-004-00082-03	 DanaEnergy
Rev. 00	Document No. SO-082-DTE-LGN-BD-CFT-0001	Page 30 of 61

- d) Comply with the regulations, rules, or code under which the container was fabricated for repairs or alterations,
- e) not be exposed to temperatures exceeding manufacturer's specifications,
- f) Not be subjected to heating methods that conflict with manufacturer's specifications,
- g) Be removed from service in accordance with the pressure vessel code under which they were manufactured for denting, bulging, gouging, corrosion, or exposure to fire, and
- h) Be marked or labeled in accordance with the requirements of the appropriate authority having jurisdiction or by agreement where no such authority exists.
- i) Certificate shall be available for which are exceeded form 5 years of manufacturer.
 - Only qualified PERSONNEL should be allowed to fill portable cylinders. Protective gloves should be worn when refilling or replacing portable cylinders.

12.10.7. FLAMMABLE/COMBUSTIBLE LIQUIDS STORAGE

- A risk assessment should be performed to determine the appropriate safe location and distance from the wellbore and appropriate safety measures for storing flammable and combustible liquids.
- Enclosed flammable or combustible liquids storage areas shall:
 - a) Maintain adequate ventilation to the outside air or engineer design to control vapors,
 - b) Have unobstructed exit(s),
 - c) Be maintained with due regard to fire potential with respect to housekeeping and materials storage,
 - d) Be identified as a hazard, and appropriate warning signs posted,
 - e) Have an appropriate fire extinguisher (see NFPA 10 for information) readily available or fixed extinguishing system installed for the hazard(s) being stored, and
 - f) Be properly classified for electrical installations in accordance with API 500 or API 505; if dispensing is done within the area, it shall be classified as Class 1, Division 1 or appropriately zoned area.
- Containers that are labeled flammable or combustible should be properly stored when not in use.

12.10.8. LIQUEFIED PETROLEUM GASES

- A risk assessment should be performed to determine the appropriate safe location and distance from the wellbore and appropriate safety measures for storing liquefied petroleum gases.
- On land locations, Liquefied Petroleum Gas (LPG) tanks larger than or totaling more than 250 gal (0.95 m³) and Liquefied Natural Gas (LNG) tanks should be placed at least 100 ft. (30.5 m) from, and parallel to the closest side of buildings (as terrain and location configuration allow) or the appropriate distance as determined by the risk assessment.

12.11. HOT WORKS, WELDING, AND FLAME CUTTING OPERATIONS

12.11.1. GENERAL (HOT WORK, WELDING, FLAME CUTTING):

- A risk assessment shall be performed and communicated by CONTRACTOR to the affected crew and other PERSONNEL (as appropriate) that determines the appropriate safe location and distance from the wellbore and other potential flammable and combustible sources, appropriate safety measures for hot work, welding, and flame cutting operations, and the requirement for a written procedure.

	Development and Production Operations Service CONTRACT for Sohrab Oil Field Well pad Construction (3,4,8) Tender No.: SO-004-00082-03	 DanaEnergy
Rev. 00	Document No. SO-082-DTE-LGN-BD-CFT-0001	Page 31 of 61

- CONTRACTOR shall ensure that Welding and flame cutting operations shall not be permitted close to flammable liquids, accumulations of crude oil, escaping gas, or locations where sparks, flames, heat, or hot slag could be sources of ignition.
- Qualified welders (certified welders where required) shall perform welding or flame cutting operations on surface facilities, piping, and equipment for which the primary function is to contain hydrocarbons or is designated critical equipment.
- Appropriate personal protective equipment shall be utilized for hot work operations.
- CONTRACTOR shall ensure that all requirement mentioned in section 8.13, for COMPANY PTW procedure and SIMOPS system will be followed for Hot Works, piping and pipeline Safety, welding, and flame cutting, etc.
- Properly maintained fire extinguishing equipment shall be available for immediate use. A minimum of at least one 30-lb (13 Kg) dry chemical fire extinguisher shall be immediately available during welding or cutting operations. This equipment is in addition to the general fire protection equipment.
- Fire watches with extinguishing equipment shall be required whenever welding or cutting is performed in locations other than designated safe welding areas.
- A fire watch shall be maintained for at least one- half hour after completion of welding or cutting operations.
- Cutting or welding shall not be permitted in the following situations:
 - A. In areas not authorized by the supervisor.
 - B. In the presence of an explosive atmosphere.
 - C. In areas near storage of large quantities of exposed readily-ignitable materials.
 - D. Where ignition can be caused by heat conduction, such as on metal walls or pipes in contact with combustibles on the other side.
 - E. On used containers such as drums unless properly cleaned.

12.11.2. EQUIPMENT (HOT WORK, WELDING, FLAME CUTTING)

- Apparatuses such as torches, regulators, hoses, and arc welding machines shall be in good operating condition and repair. Only approved and certified oxygen and acetylene cylinders shall be used.
- Oxygen and acetylene torches should be equipped with standard flash-back arrestors and approved strikers.
- All cylinders shall be equipped with a valve protection cap, a collar, or recess to protect the valve. Valve caps should be in place except when cylinders are connected for use.
- Cylinders shall be stored in assigned places away from PERSONNEL elevators, stairs, or walkways and shall be secured to prevent accidental overturning.
- Cylinders shall not be kept in unventilated enclosures, such as lockers and cupboards.
- All Gas cylinders shall have approved certification if exceeded 5 years from manufacturing date.
- Oxygen cylinders in storage shall be separated from fuel gas cylinders or combustible materials a minimum distance of 20 ft. (6.1 m) or by a noncombustible barrier at least 5 ft. (1.5 m) high having a fire-resistance rating of at least one-half hour.
- Acetylene and oxygen cylinders shall be stored valve end up with protective caps affixed and properly secured. When a job using acetylene and oxygen devices is completed or prior to transporting cylinders, the valve on the cylinders shall be closed and pressure on the hoses bled to zero.
- When transporting cylinders by a crane or derrick: a cradle, bin or other suitable platform shall be used; slings shall not be used; cylinders shall not be dropped, struck or permitted to strike each other.
- Input power terminals, top charge devices, and electrically energized metal parts shall be completely enclosed and accessible by means of tools.

	Development and Production Operations Service CONTRACT for Sohrab Oil Field Well pad Construction (3,4,8) Tender No.: SO-004-00082-03	 DanaEnergy
Rev. 00	Document No. SO-082-DTE-LGN-BD-CFT-0001	Page 32 of 61

- Terminals from welding leads shall be protected from accidental contact by PERSONNEL or metal objects. Damaged leads should not be repaired but should be immediately discarded.
- Cables with splices within 10 ft. (3.1 m) of the holder shall not be used.
- The welder should not coil or loop welding electrode cables around parts of the person.

12.11.3. WELDING FUMES AND VENTILATION

- Mechanical ventilation at the minimum rate of 2,000 ft.³/min (0.944 m³/s) per welder shall be provided when welding:
 - a) In confined spaces or where the welding space contains partitions, balconies, or other structural barriers to the extent that they significantly obstruct cross ventilation.
 - b) Where the nature of the welding, cutting, or brazing work is such that the release of toxic fumes or gases is possible. This includes work on stainless steel, zinc, lead, and degreasing or cleaning compounds containing hydrocarbons.
- Adherence to confined space entry procedures shall be followed prior to any re-entries. For example, releases from acetylene cutting equipment could change the atmosphere within the confined space.

12.12. PERMIT TO WORK (PTW)

- Prior to the commencement of work COMPANY's permit to work system and procedure shall be submitted to CONTRACTOR and make sure it is in progress. CONTRACTOR shall follow the PTW COMPANY procedure.
- Before entering the CONTRACT area, CONTRACTOR must get "WORKSITE Entrance Permission" from COMPANY at least 48 hours before starting their site activities and the minimum requirement of aforementioned permit, will be announced to CONTRACTOR at due time by COMPANY's HSE department.
- CONTRACTOR shall follow COMPANY's Permit to Work (PTW) and Simultaneous Operations (SIMOPS) procedures for all high-risk activities and other activities introduced by the COMPANY.
- Note: In case the COMPANY does not have PTW and SIMOPS procedures in place, CONTRACTOR shall develop and implement its own PTW and SIMOPS procedures and acquire the approval of the COMPANY.

12.13. LOAD LIFTING

- All lifting equipment and gears, working tools and machinery, shall be inspected and certified by approved inspection companies as per COMPANY Approved Vendor List (AVL) before entering to the WORKSITE. The use of such equipment is strictly prohibited before relevant inspection and approval. In case of any breach and violation, the operation will be stopped immediately and the relevant equipment will be removed from the site;
- The manufacturers rated load capacity shall not be exceeded on cranes or other load lifting devices. This equipment should be operated and maintained in accordance with manufacturers recommendations. Tag lines should be used to guide and steady all loads being lifted.

12.14. HOUSEKEEPING:

- During the performance of any work, CONTRACTOR shall keep the WORKSITE and its surroundings tidy, clean and reasonably free from all necessary obstructions and shall clear away and remove from the site all temporary works and surplus materials not to be used during the later stages of the work.
- CONTRACTOR shall insure that:

A. WORKSITES should be kept orderly to minimize hazards.

	Development and Production Operations Service CONTRACT for Sohrab Oil Field Well pad Construction (3,4,8) Tender No.: SO-004-00082-03	 DanaEnergy
Rev. 00	Document No. SO-082-DTE-LGN-BD-CFT-0001	Page 33 of 61

- B. Care should be taken to leave egress routes open, (especially around the plant refinery platforms and etc.).
- C. Tools, equipment, and materials should be placed and stored in a secure position or manner to prevent them from falling.
- D. Fire extinguishing equipment shall be accessible and free of obstructions during operations.
- E. Clear access to control devices, emergency shut- down, emergency equipment, etc., shall be maintained.
- F. Leaks or spills should be promptly cleaned up to eliminate PERSONNEL slipping and Fire hazards.
- Upon completion of the work, CONTRACTOR shall leave the site and PROJECT (Camp and working area) as ready for use in a clean and safe condition to the reasonable satisfaction and approved of COMPANY. Related checklist will be signed by CONTRACTOR and COMPANY.

12.15. EMBANKMENT, EXCAVATION AND TRENCHING

Trench (trench excavation)	A narrow excavation (in relation to its length) made below the surface of the ground. In general, the depth is greater than the width, but the width of a trench is not greater than 15 feet. If forms or other structures are installed or constructed in an excavation as to reduce the dimension measured from the forms or structure to the side of the excavation to 15 feet or less, the excavation is also considered to be a trench.
Excavation	Any man-made cut, cavity, trench, or depression in an earth surface, formed by earth removal mean Excavation.

- Before starting the embankment, CONTRACTOR shall consider the Mine and UXO clearance, and receive the approving clearance for working area form COMPANY's HSE and civil department.
- Before Starting the Excavation in local (in PROJECT) borrow pit area, CONTRACTOR shall Considering the Mine and UXO Clearance, and receive the approving clearance area form COMPANY's HSE and civil Department.
- Excavations such as ditches, trenches or holes shall be sloped sufficiently to prevent cave-in or slide. If sloping is impractical, shoring shall be used whenever the vertical dimension exceeds 1.5 meters.
- Worker removing shoring after completion of work shall not be in the bottom of the excavation. Shoring shall be removed in a manner to prevent cave-in on worker.
- Barricades, handrails, signals or other appropriate warning devices to protect workers from any hazardous operation or excavation shall be provided by CONTRACTOR own expense. Open trenches, excavations, etc., shall be covered when handrails or barricades do not provide adequate protection.
- Grade lines, ropes, chains, and other tripping hazards shall be sufficiently marked to be clearly visible in the day or night.
- Excavation by powered equipment closer than 1.2 meters to any underground cable is prohibited. Tiles covering electric cables shall not be removed without prior approval.
- Located underground obstacles, cables and piping shall be marked, i.e. physically identified, in the field and will be updated on drawings of underground.
- Ground water shall be removed from and kept out of, the bottoms of all trenches and excavations.
- Any excavation exceeding 1.20 meters in vertical dimensions shall be subject to issuance of work permit by CONTRACTOR.
- Before any excavation work is carried out the following procedures and actions will be carried out:
 - 1) Receive permit to work for Mine and UXO Clearance form COMPANY's HSE Department.

	Development and Production Operations Service CONTRACT for Sohrab Oil Field Well pad Construction (3,4,8) Tender No.: SO-004-00082-03	 DanaEnergy
Rev. 00	Document No. SO-082-DTE-LGN-BD-CFT-0001	Page 34 of 61

- 2) All Personnel involved, received and attend in Excavation training course and TBM conducted before starting the excavation activities.
 - 3) The ground conditions will be determined by predetermined soil analysis, boreholes or trial pits.
 - 4) Hand digging requirements will be established for exposing existing utilities. Locate underground services - check with all utility companies, look for indicator posts, use cable and pipe detectors.
- All excavations must be made safe by:
 - 1) Battering the sides to a safe angle of repose, or
 - 2) Installing structural support, e.g. trench sheets, struts, sheet piling,
 - 3) Provide edge protection for all excavations, use projecting trench sheets or other solid barriers where possible. If a person could fall more than 1.8 m, suitable barriers must be provided.
 - 4) proprietary systems or the use of drag boxes.
 - 5) Adequate lighting will be provided for any work scheduled during the hours of darkness. Consideration shall include glare factors, working in shadow and sufficient illumination to cover the area worked.
 - CONTRACTOR PERSONNEL shall be knowledgeable regarding the hazards and precautions necessary for preparing and working in trenches:

12.15.1. UNDERGROUND HAZARDS:

- When preparing an excavation, consider the hazards of underground installations. These include electrical equipment, oil and gas transmission, sewers, water lines, telephone lines and other utilities.

12.15.2. TOXIC GAS AND LOW OXYGEN HAZARDS OR/AND GAS RELEASE:

- Any trench 4 ft. (120cm) or greater in depth is usually considered "confined space". Entry into these spaces is controlled by special safety procedures where oxygen deficient or toxic gas hazards can reasonably be expected, such as near landfills or near where hazardous materials are used or stored. There is concern that heavy gases can collect inside a trench.

12.15.3. VEHICLE TRAFFIC AND FALLING LOADS:

- Vehicles on nearby roadways and construction equipment can present hazards at an excavated site. Ensure that barricades and warnings are in place.
- Construction equipment shall not lift material over people in the trench or excavation.
- The soil from the trench is also a hazard to PERSONNEL inside the trench, for this reason it must be piled at least 2 ft. from the edge of the trench.

12.15.4. STABILITY OF NEARBY STRUCTURES

- Before beginning an excavation, it is important that consideration be given to nearby buildings, light poles or other structures in the area. Additional support, installed by professionals, may be needed.

12.15.5. ESCAPE MEANS FROM TRENCHES

- A stairway, ladder or ramp should be located in any trench that is at least 4 ft. (1.2m) deep. The escape means should be placed so that a person is never more than 25 ft. away from an escape means.

	Development and Production Operations Service CONTRACT for Sohrab Oil Field Well pad Construction (3,4,8) Tender No.: SO-004-00082-03	 DanaEnergy
Rev. 00	Document No. SO-082-DTE-LGN-BD-CFT-0001	Page 35 of 61

12.15.6. INSPECTIONS

- A qualified person should inspect the trench at least daily and more frequently if needed, such as after a rainstorm or other hazardous occurrence.

12.15.7. PREVENTION OF CAVE-INS

- Any trench 5 ft. or deeper, that is not in entirely stable rock, must be sloped or shored in accordance with recognized engineering practices.

12.16. CONFINED SPACES

- CONTRACTOR shall have in place a Confined space procedure describing in detail the communication system, ERP and ERT, site emergency response operation, duties and responsibilities of PERSONNEL and action to be taken in the event of working and emergency.
- Prior to commencing work activities, a risk assessment shall be performed to determine if any confined spaces exist or will be created as a result of work at the site. Cellars, excavations, and other confined areas often meet the definition of a confined space.
- Spaces that are determined to be confined spaces shall be assessed to determine if any of the following hazards exist or have the potential to exist:
 - a) Hazardous atmosphere;
 - b) Potential for engulfing an entrant;
 - c) Internal configuration such that an entrant could be trapped or asphyxiated by inwardly converging walls or by a floor which slopes downward and tapers to a smaller cross-section, or
 - d) Other recognized safety or health hazard(s).

12.17. NON-DESTRUCTIVE TESTING (NDT) AND RADIATION PROTECTION

- CONTRACTOR shall implement the Radiation Safety procedure and perform a risk assessment before starting nondestructive testing (NDT) the activity.
- CONTRACTOR shall ensure that all of its activities related to radiological risks in PROJECT shall comply with governmental laws, regulations and instructions of Atomic Energy Organization of Iran (ICRP) and COMPANY.
- When using Non-Destructive Testing (NDT) methods, qualified and certified persons should conduct the tests in accordance with recognized methodology and acceptance criteria. Certified NDT inspectors shall be trained per ASNT RP No. ASNT-TC-1A.
- CONTRACTOR shall insure that all activities in this category shall have documented permission from COMPANY representative manager and inform HSE department in advance.
- CONTRACTOR shall identify, control and monitor all the risks of radiation activities.
- CONTRACTOR shall use expert PERSONNEL with proper certificate for radiography activity.
- CONTRACTOR shall follow the Exposure Limits procedure for Radiation Workers and the Public.
- CONTRACTOR shall provide full NDT PPE and safety and warning signs for his PERSONNEL and working area at its own expense.
- CONTRACTOR shall at its own expense submit and provide related NDT certificates to the COMPANY and provide all necessary equipment for controlling the NDT activity including but not limited to warning lights and sine, X ray dosimeter, X ray radiometer etc.

	Development and Production Operations Service CONTRACT for Sohrab Oil Field Well pad Construction (3,4,8) Tender No.: SO-004-00082-03	 DanaEnergy
Rev. 00	Document No. SO-082-DTE-LGN-BD-CFT-0001	Page 36 of 61

12.18. EMERGENCY ACTION PLAN AND RESPONSE

- CONTRACTOR shall have in place an Emergency Response Plan (ERP) and action plan describing in detail the communication system, ERP Policies, site emergency response operation, duties and responsibilities of PERSONNEL and action to be taken in the event of an emergency.
- The CONTRACTOR ERP, which is to be consistent with the COMPANY ERP, shall be reviewed and approved by the COMPANY prior to the commencement of the works.
- CONTRACTOR shall where applicable at its own expense provide adequate first aid, firefighting, lifesaving and other safety equipment and shall maintain this equipment in a professional manner and where appropriate recertify as dictated by legal and industry standards.
- CONTRACTOR shall keep up-to-date records of all said equipment, including equipment location plans and layout.
- CONTRACTOR shall ascertain that emergency procedures are well understood; efficient drills and exercises shall regularly be carried out on the WORKSITE and related report send to COMPANY.
- Drills and exercises as follow but not limited to:
 - A. Road traffic accident;
 - B. Fire;
 - C. H2S and gas release or leak, evacuation, Man lost;
 - D. Working at height rescue;
 - E. Radiation leak;
 - F. Storm;
 - G. Blow-out;
 - H. Medevac;
 - I. Environmental spill (oil, chemicals);
 - J. Other necessary ERP procedures.

12.19. SECURITY

- CONTRACTOR shall ensure that all its employees and those of subcontractors fully comply with COMPANY outlined security requirements and rules.
- At all times during the performance of the Work, CONTRACTOR shall take all necessary precautionary measures and shall conduct all activities under the Contract in a manner to minimize the risk of loss, theft, sabotage, damage by vandalism or otherwise howsoever to any property.
- In accordance with COMPANY's policy, CONTRACTOR's Personnel are required to possess an official pass card while on any COMPANY premises and worksite.
- CONTRACTOR shall take full responsibility about the security issues of its PERSONNEL all the time.
- CONTRACTOR shall enhance the security management in the Contract Area; take necessary escort for night shifting PERSONNEL and be sure that the main gates is well controlled by well-trained guards.
- Mobile phone; For safety reasons mobile phones will not be allowed on any Production restricted areas without the specific authority of the COMPANY Site Representative.
- CONTRACTOR shall follow the COMPANY security and military regulation on PROJECT.
- CONTRACTOR Personnel shall not be allowed to be at the Worksite without Approval by COMPANY.

12.20. LOCK-OUT/TAG-OUT (LOTO - ENERGY ISOLATION)

- CONTRACTOR shall have insured that, a documented lock-out/tag-out program shall be established and implemented.

	Development and Production Operations Service CONTRACT for Sohrab Oil Field Well pad Construction (3,4,8) Tender No.: SO-004-00082-03	 DanaEnergy
Rev. 00	Document No. SO-082-DTE-LGN-BD-CFT-0001	Page 37 of 61

- CONTRACTOR PERSONNEL should be trained and disciplined in the use of this system to prevent unexpected operation of any equipment that stores any type of energy that might inflict injury to PERSONNEL.
- CONTRACTOR shall ensure that the lock or tag should be removed by the person who installed it. In the event the individual is not available, the lock or tag may be removed by the supervisor after ensuring that no hazard will be created by energizing the locked or tagged equipment or circuit(s).
- Prior to performing work on equipment where energy isolation has been applied, the equipment shall be tested to verify (try out) that energy isolation is successful and stored energy has been released. Confined Spaces, Excavations, and Hazardous Environments.

12.21. PIPELINE SAFETY:

12.21.1. DESIGN OF A PIPELINE

- The CONTRACTOR shall ensure that all designs are in accordance In compliance with COMPANY and contractual requirements and standards.
- The CONTRACTOR shall ensure to contract no fluid is conveyed in a pipeline unless it has been so designed that, so far as is reasonably practicable, it can withstand :
 - A. forces arising from its operation;
 - B. the fluids that may be conveyed in it; and
 - C. the external forces and the chemical processes to which it may be subjected.

12.22. WORK IN PROXIMITY TO EXPOSED ENERGIZED POWER SOURCE AND ELECTRICAL SYSTEM EQUIPMENT

- CONTRACTOR shall ensure that, electrical equipment used in hazardous locations should be designed for such locations, and approved by a nationally recognized testing laboratory, or country equivalent (refer to API 500 or 505 for classification of areas as hazardous locations for electrical equipment). Wiring components and electrical equipment should be maintained in accordance with the manufacturer's recommendation.
- Wiring should be protected from abrasion, vehicular and foot traffic, burns, cuts, and damage from other sources.
- Wiring, including insulation, should be replaced, properly repaired, or sealed as necessary, when damage is detected.
- Extension cords shall be fit for purpose, properly insulated, and in good condition.
- Neither equipment or machines shall be operated closer to power lines than the recommended minimum clearances shown in Table 2, except when such lines have been DE energized and visibly grounded or when barriers are present to prevent physical contact with the lines.
- An individual should be designated to observe equipment clearance as defined in Table 2. The operator should notify the observer if he is having any difficulty in determining the clearance. The observer should sound a warning at any time the clearance is not maintained.
- Overhead wires should be considered energized (live) unless either the electrical system owner reports them to be non-energized, or a qualified electrical person tests and finds them to be non-energized.

Equipment	Line Voltage, Volts	Minimum Clearance
-----------	---------------------	-------------------

	Development and Production Operations Service CONTRACT for Sohrab Oil Field Well pad Construction (3,4,8) Tender No.: SO-004-00082-03	 DanaEnergy
Rev. 00	Document No. SO-082-DTE-LGN-BD-CFT-0001	Page 38 of 61

Operating	All	10 ft. plus 4 in. for each additional 10 kV over 50 kV
In transit	less than or equal to 50 kV	4 ft.
	greater than 50 kV	4 ft. plus 4 in. for every additional 10 kV

Table 2—Recommended Minimum Clearances Between Power Lines and equipment or and machinery.

13. ENVIRONMENT WASTE MANAGEMENT

- In the performance of the services, CONTRACTOR shall at all times follow Project EIA (Environment Impact Assessment) requirements, follow Islamic Republic Iran Laws, DOE (Department of Environment), NIOC regulations and COMPANY's waste management regulations and procedures and act to minimize the quantity of waste and shall observe and comply with all related laws and regulations concerning the production, carrying, keeping, treating and/or disposal of waste and the following specific environmental considerations where appropriate:
 - a) CONTRACTOR shall not use ozone-depleting substances or products with known global warming potential.
 - b) CONTRACTOR shall demonstrate a management strategy to minimize environmental impact of chemicals through correct selection, use and disposal.
 - c) CONTRACTOR shall not discharge any chemicals/sewage/garbage to land or sea.
 - d) CONTRACTOR at his own cost shall suitably remove and dispose of garbage, unused hazardous substances and scraps in accordance with environmental regulations and codes and COMPANY requirements.
- In the course of the WORKS under the CONTRACT, the CONTRACTOR shall take all necessary safety measures to ensure the protection of the environment, atmospheric air, surface and ground waters, soils and grounds, subsoil, fauna and flora from adverse effects caused by the actions of the CONTRACTOR and to minimize the damage, which may entail such actions.
- As Sohrab Oil Field is situated in the environmental protected areas under custody of Department of Environment (DOE), CONTRACTOR is obligated to perform all works and activities in accordance with environmental rules, regulations and procedures to avoid any environmental contamination and damages. CONTRACTOR shall be responsible to pay fines subjected to COMPANY regarding this matter;
- A copy of CONTRACT with waste transportation and handling SUBCONTRACTORS shall be handed over to the COMPANY's HSE department up on request. Any violation of Iranian or international environmental laws, regulations, which leads to damaging the environment or any cost occurred due to this damage will be CONTRACTORS' responsibility.
- The following environmental issues should be considered as part of a comprehensive assessment and management program that addresses PROJECT specific risks and potential impacts. Potential environmental issues associated with onshore oil and gas development PROJECTs include the following:

	Development and Production Operations Service CONTRACT for Sohrab Oil Field Well pad Construction (3,4,8) Tender No.: SO-004-00082-03	 DanaEnergy
Rev. 00	Document No. SO-082-DTE-LGN-BD-CFT-0001	Page 39 of 61

- Air emissions;
- Wastewater discharges;
- Solid and liquid waste management;
- Noise generation;
- Terrestrial impacts and PROJECT footprint;
- Impacts on subsoil and aquifers;
- Oil /chemical spills;
- Spill Response Planning; and Energy efficiency and resource conservation.

13.1. WATER CONSUMPTION AND DISCHARGES TO LAND AND AQUATIC ENVIRONMENT

- When performing the WORKS under the CONTRACT, the CONTRACTOR shall take the necessary measures to reduce water consumption.
- The CONTRACTOR shall allocate funds and resources in the required amount and organize the process of water consumption, sewerage and disposal of effluents in such a way as to exclude the discharge of liquids (fluids) or substances (reagents) to the terrain and into water bodies (without an appropriate discharge permit).
- The CONTRACTOR shall be fully liable for disinfection and removal to the place of the final point of disposal of effluents generated as a result of the life activity of the CONTRACTOR and its SUBCONTRACTORS.
- At the same time, the costs incurred by the CONTRACTOR for disinfection, transportation and disposal of wastewater by the COMPANY shall not be reimbursed.
- All spills of pollutants and other accidental discharges to land shall be eliminated, the territory affected by the negative impact shall be cleaned up by the CONTRACTOR. To eliminate possible spills, the CONTRACTOR shall have all the necessary equipment and materials, as well as trained PERSONNEL or the availability of concluded contracts with specialized organizations.
- CONTRACTOR shall maintain primary accounting for water consumption and water disposal. On a monthly basis, the HSE Service of the COMPANY shall be provided with a certificate with data on water consumption and water disposal on the basis of primary accounting, in accordance with the requirements of the legislation of Iran and internal requirements of the COMPANY.
- The COMPANY shall not reimburse the CONTRACTOR's expenses for making payments for water consumption.
- In case of ensuring the transportation of effluents from the CONTRACTOR's vital activities by the COMPANY, the CONTRACTOR shall compensate the costs incurred by the COMPANY in full according to the documents provided.

13.2. ATMOSPHERIC EMISSION

- When performing the WORKS under the CONTRACT, the CONTRACTOR shall take the necessary measures to reduce emissions of pollutants into the atmosphere from stationary and mobile sources.
- The CONTRACTOR is obliged to organize regular maintenance of vehicles and installations (including boiler houses) to comply with the emission quality standards.
- Incineration of any type of waste by the CONTRACTOR shall be performed only with the prior approval of the COMPANY.

	Development and Production Operations Service CONTRACT for Sohrab Oil Field Well pad Construction (3,4,8) Tender No.: SO-004-00082-03	 DanaEnergy
Rev. 00	Document No. SO-082-DTE-LGN-BD-CFT-0001	Page 40 of 61

13.3. WASTE MANAGEMENT AND REDUCTION

- When performing the WORKS under the CONTRACT, the CONTRACTOR shall take the necessary measures to reduce the generation of waste.
- The CONTRACTOR shall arrange:
 - a) Separate collection and accounting of waste in accordance with the hazard class and properties of waste;
 - b) Temporary storage in specially designated areas;
 - c) suitable means (in the required amount) for the collection and/or storage of waste for each hazard class;
 - d) As well as disposal of production and consumption waste (removal of household and construction waste, food waste, scrap metal, etc.) generated as a result of the CONTRACTOR's activities upon completion of the WORKS.
 - e) Assigning a local team to housekeeping and collecting scattered wastes in the WORKSITE related to the CONTRACTOR and its subcontractors.
- CONTRACTOR will prepare a Waste Management Plan. This plan will be used by the CONTRACTOR throughout the PROJECT to manage the environmental matters.
- CONTRACTOR(s) must consider Waste Management as one of the important aspects of their HSE performance and establish a compiled procedure for all different kinds of waste handling.
- CONTRACTOR must follow COMPANY Waste Management Plan regulation; all the transportation of waste (manifest) must have signed note. The note also must be signed by the received point.
- The CONTRACTOR shall be fully liable for the disposal of waste accumulated as a result of its production and life activities.
- The CONTRACTOR shall independently and at its own expense enter into contracts for the transportation, disposal of its own waste and the waste of the SUBCONTRACTORS to the place of disinfection and disposal.
- At the same time, the costs incurred by the CONTRACTOR for temporary storage, transportation of waste to the place of disposal and their subsequent disinfection by the COMPANY shall not be reimbursed.
- For each type of waste, a hazard class must be determined and appropriate storage conditions must be arranged.
- Waste manifest and bill of loading shall be used to transfer the waste to approved location.
- An agreement shall be available between the CONTRACTOR and Nearest Municipality organization for transferring the wastes and related document shall be sub-mitted to COMPANY.
- The CONTRACTOR is obliged to keep primary accounting of waste generation and movement in accordance with the requirements of the legislation of Iran or internal requirements of the COMPANY.
- It is forbidden to incinerate waste outside the established places and/or on equipment that does not have permits and approved technology for waste disposal, as well as to bury waste.
- In case of establishing the fact of illegal disposal or burial of waste by the CONTRACTOR, the CONTRACTOR shall compensate the COMPANY for the losses incurred for damages on the basis of a bilateral act and a corresponding claim.
- The establishment of the fact of illegal disposal or burial of waste by the CONTRACTOR or its SUBCONTRACTOR shall be confirmed by the relevant act (Attachment 2) or the order of the COMPANY, regulatory or supervisory authorities. In this case, the CONTRACTOR shall reimburse the COMPANY for the losses incurred due to fines, damages, etc. issued by the supervisory authorities.
- If the removal and disposal of waste is carried out by the COMPANY or to the COMPANY REPRESENTATIVE.

	Development and Production Operations Service CONTRACT for Sohrab Oil Field Well pad Construction (3,4,8) Tender No.: SO-004-00082-03	 DanaEnergy
Rev. 00	Document No. SO-082-DTE-LGN-BD-CFT-0001	Page 41 of 61

13.4. BIODIVERSITY

- The CONTRACTOR is obliged to take all necessary actions to protect the flora and fauna in the course of the WORKS, including minimizing the clearance of the territory required for the WORKS.
- Hunting, fishing, swimming and diving are strictly prohibited in environmental protected areas.
- Prior to clearing the territory, the CONTRACTOR shall mark the boundaries of the site where the WORKS will be performed with flags or poles, and ensure that no clearing is performed outside this territory. Prior to the start of clearing, the boundaries of this territory shall be agreed with the COMPANY.
- The CONTRACTOR shall exclude the cutting of trees and bushes in the territory of the WORKS.
- Off-road driving is prohibited, vehicles should move only on designated areas and constructed roads.
- The CONTRACTOR shall use the existing utilities and access roads, where available, and minimize the damage to the environment.

13.5. SPILLS OF OIL AND FUEL AND LUBRICANTS

- The CONTRACTOR shall ensure that all practical measures are taken in order to minimize the likelihood and consequences of spills of oil and lubricants during the performance of the WORKS under the CONTRACT, including:
 - provision of equipment for control of spills and materials for their removal (barriers, scoops, shovels, sorbents, bags, etc.) at the working site;
 - spill response procedures;
 - trained PERSONNEL of the CONTRACTOR, able to prevent and respond in time to spills of oil and fuel and lubricants;
 - regular maintenance and inspection of the machinery, vehicles and equipment for possible leaks.
- The CONTRACTOR shall be fully liable for spills at the site of the WORKS.
- In the event of a spill of oil products and other substances on the territory of the COMPANY during the WORKS, the CONTRACTOR shall at its own expense restore the territory to its original state.
- The CONTRACTOR is obliged to prevent the subsequent spread of spilled substances throughout the territory, using its own capabilities.
- The CONTRACTOR shall immediately notify the COMPANY about spills with the following details:
 - A. area (volume) of spilled materials;
 - B. spill location;
 - C. Spill combatting plan;
 - D. ability to limit spreading;

13.6. ENVIRONMENTAL PROTECTION MEASURES

13.6.1. WATER PROTECTION ZONES:

- The CONTRACTOR is obliged to familiarize itself with the water protection zones on the territory of the WORKSITE and take all necessary measures so as not to damage these zones in the course of the WORKS. These include the following measures:
 - The CONTRACTOR shall use signs to designate water protection zones;
 - Tree cutting is prohibited in water protection zones;
 - Car traffic should also be reduced to a minimum in water protection zones;
 - Storage of harmful substances (fuels and lubricants, etc.) is not allowed;
 - No gas stations are allowed;
 - Storage and burial of solid and liquid waste is not allowed;
 - Car repair activities are not allowed;

	Development and Production Operations Service CONTRACT for Sohrab Oil Field Well pad Construction (3,4,8) Tender No.: SO-004-00082-03	 DanaEnergy
Rev. 00	Document No. SO-082-DTE-LGN-BD-CFT-0001	Page 42 of 61

- Parking of cars is prohibited;
- No camping is allowed.

13.6.2. SOIL LAYER:

- The CONTRACTOR shall take all necessary measures to preserve the integrity and structure of the soil, which is adversely affected during the performance of the WORKS.
- The CONTRACTOR shall separate the upper soil layer from the subsoil layer during the WORKS of the excavator and also keep these layers separately until the subsequent reclamation.
- In the course of reclamation, the CONTRACTOR shall evenly distribute the soil layer during backfilling and reclamation of the WORKSITE.
- The CONTRACTOR shall ensure that the soil layer is properly laid and rolled in order to avoid the possibility of soil erosion.

13.6.3. NOISE:

- The CONTRACTOR shall take all possible measures to minimize the noise level in the course of the WORKS, which include:
 - Performance of the WORKS at a time when noise causes the least disturbance, and only in case of industrial necessity;
 - Use of well-maintained equipment;
 - Use of equipment with mufflers, where possible.

13.6.4. LIGHTING:

- The CONTRACTOR shall take all possible measures to minimize the negative impact of light on the environment during the performance of the WORKS. These include the following measures:
 - Avoid the use of spotlights;
 - Provide all sources of bright light with protective visors and direct the light downward;
 - Use, if possible, dim lighting for non-permanent use (for example, the use of sodium lamps along roads and driveways).

13.6.5. SEPTIC TANK

- The CONTRACTOR shall provide septic and utilization of the sewage water approved by COMPANY, waste management any other utilities for accommodations by its own cost.
- Accommodations should be planned in a manner that they are at least at a distance of 20 meters from the septic tanks and soak pits.
- Septic tank and soak-away pit should be covered and provided with proper vents. All septic tank shall be insulated and designed to avoiding the leakage in the environment and/or follow the COMPANY septic tank specification and drawings.
- Septic Tank (Non-absorption type): polyethylene septic tanks (each with the capacity of 25,000 liters) shall be constructed in specified area in accordance with approved drawing and procedure.
- CONTRACTOR shall follow the COMPANY Environmental requirements.

13.6.6. SEWAGE WATER

- The sewage water from both camp and WORKSITE should be treated by Sewage Treatment Plant according to Iranian Department of Environment law.
- Sewage water manifest and bill of loading shall be used to transfer the sewage to approved location.

	Development and Production Operations Service CONTRACT for Sohrab Oil Field Well pad Construction (3,4,8) Tender No.: SO-004-00082-03	 DanaEnergy
Rev. 00	Document No. SO-082-DTE-LGN-BD-CFT-0001	Page 43 of 61

- An agreement shall be available between the CONTRACTOR and Nearest Water and waste water organization for transferring the wastes and related document shall be sub-mitted to COMPANY.

14. HSE Requirements of camps and workshops

14.1. CAMP STANDARDS

- At the time of bidding The CONTRACTOR will provide a detailed layout of its proposed camp for COMPANY approval prior to commencing any work on it. This detailed layout will include details of messing facilities, sleeping quarters, cooking arrangement, storage areas (food, water & supplies).
- The camp will conform to the following minimum standards:
 1. Adequate lighting would be provided in the camp area especially main gate, around kitchen, toilets, fence boundaries and mess area.
 2. Policies of the COMPANY and CONTRACTOR should be posted at prominent places.
 3. Proper Safety awareness signs should be posted all around the camp rea

14.2. CAMP HYGIENE

- A dedicated camp boss should be designated to carry out daily inspections of the entire camp for maintaining camp hygiene.
- Camp area should have adequate number of waste baskets for collection of garbage.
- CONTRACTOR shall ensure that portable water for the camp is certified fit for purpose by a reputable 3rd Party. Alternative arrangements such as approved bottled water should be in place.
- Disinfection should be carried out on a regular basis.
- Microbial, Chemical and physical tests (1053) of portable water shall be done on regular basis and result shall be submitting to COMPANY.
- Adequate number of janitorial staffs should be available to provide highest possible level of hygiene.
- Regular complete fumigation of camp to be carried out as per Expertise.

14.3. ACCOMMODATIONS

- Accommodation shall be such that it provides protection against wind, rain and extreme temperatures.
- Accommodation shall be adequately screened against insects.
- A minimum sleeping space of 4 square meters per person is recommended.
- Accommodations should preferably be provided in Porta-cabins for camps and offices.
- Each Porta-cabin or Prefabricated House for Site Temporary Porta Cabin Camps and offices should be properly grounded and equipped with Residual Current Circuit Breaker (RCCB).
- Each Porta cabin or Prefabricated House for Site Temporary Porta Cabin Camps and offices should have portable smoke detectors in working conditions.
- Proper hygiene should be maintained for each Porta cabin on a daily basis
- Proper illumination of living/ working area to avoid snake bites etc.
- A/C (s) is to be provided in all accommodation's cabins.

14.4. KITCHEN AREA & FOOD STORAGE

- CONTRACTOR shall follow the COMPANY and legal procedures of Ministry of Health and Medical Education of I.R. Iran for Kitchen area and food storage.
- Kitchen should be in a Porta-cabin or Prefabricated House for Site Temporary Porta Cabin Camps.
- All staff shall have approved and valid Health certificate.
- A risk assessment should be performed on the cooking area prior to mobilization.

	Development and Production Operations Service CONTRACT for Sohrab Oil Field Well pad Construction (3,4,8) Tender No.: SO-004-00082-03	
Rev. 00	Document No. SO-082-DTE-LGN-BD-CFT-0001	Page 44 of 61

- Cooking is not permitted in tents or outside of Porta Cabin or buildings.
- Bonfires are strictly prohibited.
- If Gas cylinders are used for cooking, those shall be secured properly, to avoid any accident.
- Additionally, all of the gas cylinders shall be placed outside the kitchen by making proper areas/ ditches for their support and provision of proper shades.
- Proper burners shall be used for cooking with stable and correctly sized pan supports.
- All food storage shall be kept in closed containers.
- Cleaning detergents or other unwanted materials / chemicals shall not be kept in food store.
- Proper and enough Fire blanket and fire extinguishers are to be provided.
- Frozen meat received at the camp should be properly tagged for its date of production.
- CONTRACTOR to ensure food items for at least one week in stock.

14.5. MESS AREA

- Messes should be in a Porta-cabin.
- Messes timings shall be maintained.
- Policies shall be posted on the notice boards.

14.6. CHEMICAL STORAGE

- All cleaning / washing chemicals should be kept separate from food storage.
- Safety Data Sheets (SDS) of all chemicals at site should be available.
- All chemicals / detergent containers shall be labeled, for their contents.
- CONTRACTOR shall follow the Chemical handling procedure.

14.7. TOILET, SANITARY FACILITIES & LAUNDRY

- Sufficient toilet and washing facilities shall be provided and shall be hygienically maintained.
- Washable (e.g. cement) flooring is recommended.
- Laundry facilities shall be provided.
- All laundry equipment (washing machine, etc.) should be properly earthed.
- Personal Protective Equipment (PPE) like gloves should be worn, while handling laundry chemicals.
- CONTRACTOR shall follow the COMPANY and legal procedures of Ministry of Health and Medical Education of I.R. Iran for toilet, sanitary facilities and laundry.

14.8. ELECTRICAL SYSTEM

- The camp will need electricity, whose generation and distribution needs to be handled with utmost care. The following minimum standards not limited to, will apply to all electrical systems operated by the CONTRACTOR during the execution of the CONTRACT:
 1. All generators should be placed on a concrete pad with proper bunding arrangements.
 2. A standby generator for meeting at minimum camp requirements should be available.
 3. All generators should be properly earthed as per internationally acceptable procedures.
 4. A qualified and competent person should maintain and operate generators.
 5. Generator area should be out of bounds, for all PERSONNEL, except for the operator.
 6. All electrical wires should be in PVC conduits when they are exposed to high physical wear or high ambient temperatures.
 7. Splicing is not allowed in the camp electrical wiring, connections must be through a junction box.
 8. All of the electrical wiring shall be distributed in a safe manner i.e. properly buried according to international standards or in proper cable trays.
 9. Hanging of energized wires shall be avoided.

	Development and Production Operations Service CONTRACT for Sohrab Oil Field Well pad Construction (3,4,8) Tender No.: SO-004-00082-03	 DanaEnergy
Rev. 00	Document No. SO-082-DTE-LGN-BD-CFT-0001	Page 45 of 61

10. All of the cables should be properly coated to avoid any leakage.
11. No electric wires shall be spread on the surface in open, which can become a tripping hazard.
12. All Junction Boxes should be weather resistant and possess proper sealing arrangements.
13. The neutral in the camp electrical distribution will be connected to earth at source.
14. A separate earth wire will be used to earth all metallic enclosures.
15. Wiring in wet areas (shower and washrooms) shall comply with standards for such areas.
16. A clearly identified and accessible means of isolation shall be provided for each caravan, unit or trailer.
17. Warning signs shall be posted and available.
18. All generators, Distribution Boxes, main switches and distribution network will have to be certified by third party (at CONTRACTOR's own cost) as certified fit for purpose and conforming acceptable international standards before mobilization.

14.9. VEHICLE MAINTENANCE AREA

- CONTRACTOR shall consider the mentioned requirements:
 - 1) If the vehicles are to be repaired, they shall be carried out at a designated area, This area should be cemented and bunded.
 - 2) Provide drip trays in case the nature of job is for a very limited time frame.
 - 3) No open oil drainage should be done in or outside the camp.
 - 4) Used oil should be collected in drums and disposed off through approved venders to fulfill international and local standards requirements.
 - 5) Used oil filters and other maintenance waste shall be segregated and disposed through approved venders to fulfill international and local standards requirements.
 - 6) CONTRACTOR shall follow the COMPANY Environmental requirements and procedures.

15. LIQUIDATED DAMAGES

- CONTRACTOR and SUBCONTRACTOR s are responsible for correcting to COMPANY satisfaction any deficiencies noted or any Non-Conformity Report (NCR) in the HSE audit/inspection programs (refer to HSE Audit Procedure SO-000-DMS-HGM-HS-PRC-0053). Failure to comply with audit/inspection findings can cause work to be halted with severe contract LIQUIDATED DAMAGES for failure to comply with corrective action mandates.
- If the CONTRACTOR does not observe the HSE criteria specified in the contract, and Iran work regulations, standards at all stages of the project, COMPANY REPRESENTATIVE has right to cease and stop the work or hold permission to start execution and hold payments and apply LIQUIDATED DAMAGES on the CONTRACTOR, which aggregate amount of LIQUIDATED DAMAGES in HSE section shall not exceed Two percent (2%) of the ceiling CONTRACT PRICE.
- In the event of any violation by CONTRACTOR, COMPANY will give notice or warning to CONTRACTOR for rectifying the problem(s) within specified time schedule (according to prior notice). If CONTRACTOR neglects COMPANY notification, NCRs and does not take Corrective action, COMPANY has the right to impose LIQUIDATED DAMAGES on CONTRACTOR up to Zero-Point One percent (0.1%) of ceiling CONTRACT price, for each case without prejudice to CONTRACTOR's other obligations stipulated in the CONTRACT.
- The CONTRACTOR's refusal or inability to remedy any hazardous safety or environmental working practice, or to perform the required modification to its equipment within stipulated time period and in the case of contractual HSE requirements breaches, the COMPANY may terminate the CONTRACT.

Scale of LIQUIDATED DAMAGES – but not limited to the following – to the CONTRACTOR for violation of the HSE requirements:

Table 1 HSE LIQUIDATED DAMAGES

	Development and Production Operations Service CONTRACT for Sohrab Oil Field Well pad Construction (3,4,8) Tender No.: SO-004-00082-03	 DanaEnergy
Rev. 00	Document No. SO-082-DTE-LGN-BD-CFT-0001	Page 46 of 61

Examples of HSE Non-Compliances	Measures	Description of measures and fines
Observation of limited cases of classified audit founding's, minor (Low and Medium according to COMPANY HSE Audit Procedure SO-000-DMS-HGM-HS-PRC-0053) non-compliance with HSE in CONTRACTOR's performance	Written notice	Notification of written notice without imposition of a fine
Observation of a case of audit founding's, major (High and Serious according to COMPANY HSE Audit Procedure SO-000-DMS-HGM-HS-PRC-0053) noncompliance with HSE observation of multiple instances of minor (Low and Medium) non-compliance with HSE in CONTRACTOR's performance Incidence of minor events caused due to CONTRACTOR's fault/failure	First notice	Notice of non-compliance Two percent (2%) of current statement/ invoice amount shall be deducted from the current statement/invoice and/or any other amounts due to the Contractor.
Observation of multiple instances of audit founding's, major High and Serious according to COMPANY HSE Audit Procedure SO-000-DMS-HGM-HS-PRC-0053) non-compliance with HSE in CONTRACTOR's performance Incidence of debilitating events due to CONTRACTOR's fault/failure	Second notice	Five percent (5%) of current statement/ invoice amount shall be deducted from the current statement/invoice and/or any other amounts due to the CONTRACTOR.
Major weakness in CONTRACTOR's HSE Management System (MS) and incidents leading to death due to CONTRACTOR's fault/failure	Third notice	Ten percent (10%) of current statement/ invoice amount shall be deducted from the current statement/invoice and/or any other amounts due to the CONTRACTOR Referring the CONTRACTOR's default to the COMPANY's Representative for making appropriate decision about termination of CONTRACT.

15.1. Life Saving Rules Enforcement

Breaching Life Saving Rules will attract disciplinary action(s) up to termination of CONTRACTOR's employees. The level of consequences given to the individual will be guided as per Consequence Matrix below (Table);

	Development and Production Operations Service CONTRACT for Sohrab Oil Field Well pad Construction (3,4,8) Tender No.: SO-004-00082-03	 DanaEnergy
Rev. 00	Document No. SO-082-DTE-LGN-BD-CFT-0001	Page 47 of 61

Table 2 Life Saving Rules Violation and Consequence

Life Saving Rules Violation and Consequence Matrix													
Twelve Life Saving Rules			Rule is broken for the first time		Rule is broken for the second time		Rule is broken for the third time	Several rules are broken at the same time	Rule -breaking caused injury or death or was done willfully				
			Low potential for injury	High potential for injury	Low potential for injury	High potential for injury							
Work Authorization	Confined Space	Line of Fire	Verbal warning	Warning Letter	Warning Letter	Final Warning Letter	Dismissal/Remove from site	Final Warning Letter	Dismissal/ Remove from site				
Working At Height	Hot Work	PPE											
	Excavation	Safe Mechanical Lifting	Warning Letter		Final Warning Letter		Dismissal/Remove from site						
	Driving	Bypassing Safety Controls											
			Energy Isolation										
		Use of Alcohol and Illegal Drugs	Dismissal / Remove from site										

	Development and Production Operations Service CONTRACT for Sohrab Oil Field Well pad Construction (3,4,8) Tender No.: SO-004-00082-03	 DanaEnergy
Rev. 00	Document No. SO-082-DTE-LGN-BD-CFT-0001	Page 48 of 61

Table 2: Some instances of non-compliance including the CONTRACTOR's violation of the provisions/fault and refusal to comply with HSE implementation

Row	Description of the violation
1	Failure to supply HSE PERSONNEL
2	Failure of CONTRACTOR's PERSONNEL to use Personal Protective Equipment
3	Unsafe, risky actions by the CONTRACTOR's PERSONNEL
4	Failure of CONTRACTOR's vehicles to comply with transportation regulations
5	The use of equipment and tools not approved by the COMPANY HSE representative
6	Burning of wastes in Project
7	Hunting and fishing in DOE Protected area
8	Disposal of contaminated fluids/hydrocarbon substances Project
9	Disposal and discharging any kind of wastes in the DOE protected areas and Project
10	The incidence of major explosions/fires due to CONTRACTOR's failure
11	Destruction of flora and fauna at DOE protected area and Project
12	Taking water from DOE protected area
13	Failure to comply with Environment requirements
14	Lack of design and implementation of control measures for the significant risks identified during the term of contract, based on the HSE Plan
15	Failure to install required HSE equipment
16	Failure to comply with Health requirements
17	Failure to conduct periodic medical examinations (Fitness For Work).
18	The incidence of poisoning due to the consumption of unhealthy water and food in the scope of the CONTRACTOR's liability
19	Failure to develop and implement HSE MS
20	The occurrence of lost time injuries within the CONTRACTOR's scope of work
21	The occurrence of incidents leading to death within the CONTRACTOR's scope of work
22	Noncompliance with DOE rules and regulations
23	Noncompliance with local authorities' rules and regulations
24	Fatality incident case/permanent and partial disabilities case/ more than three Lost Time Injury Cases per year or more than one Lost Time Injury Case per month
25	Repetition of other levels of incidents (MTCs, RWCs, FACs, Asset Damage, ...) in such a way as to indicate the negligence of the CONTRACTOR at the discretion of COMPANY HSE department
26	Lack of procedure or failure to the implementation of the HSE policies, plans and procedures during the execution of the WORK under the CONTRACT
27	Violation of any of the Health/Safety/Environment provisions, terms and conditions stipulated in Section 4 and Section 6 of the CONTRACT.

	Development and Production Operations Service CONTRACT for Sohrab Oil Field Well pad Construction (3,4,8) Tender No.: SO-004-00082-03	 DanaEnergy
Rev. 00	Document No. SO-082-DTE-LGN-BD-CFT-0001	Page 49 of 61

15.2. DRIVER DISCIPLINARY PROCEDURE

Disciplinary procedure for CONTRACTOR and SUBCONTRACTOR drivers is a three-step rule as follows:

- 1) Verbal warning.
- 2) Written Warning
- 3) Dismissal

Intention of the Three Step Rule is corrective action for individuals who violate their responsibilities / privileges. It is the responsibility of the appropriate CONTRACTOR and SUBCONTRACTOR Manager or supervisor to administer a warning. When violations occur, the CONTRACTOR Manager / Supervisor will investigate the incident and administer the warning based on their findings.

An individual Step has a time limit of 12 months. After the elapse of this time warning will be removed from future consideration unless otherwise specified by the CONTRACTOR and SUBCONTRACTOR Manager / Supervisor.

Strike 1 – Verbal Warning

The first occurrence of any CONTRACTOR and SUBCONTRACTOR violation of the HSE and driving Policy will result in a verbal warning. The violator is to be counseled by the respective CONTRACTOR and SUBCONTRACTOR Manager / Supervisor.

Strike 2 – Written Warning

The second occurrence of any CONTRACTOR and SUBCONTRACTOR violation of HSE and driving Policy will result in a written warning. The CONTRACTOR and SUBCONTRACTOR Line manager shall counsel the violator.

Immediate participation in a driver re-assessment may be required after the first or second Strike if the CONTRACTOR and SUBCONTRACTOR Manager/Supervisor believes the violator lacks competency.

Strike 3 – Dismissal

The third occurrence of any CONTRACTOR and SUBCONTRACTOR violation of HSE and driving Policy will result in the dismissal of the driver. It is to ensure that a disciplinary procedure for drivers is in effect and documented.

	Development and Production Operations Service CONTRACT for Sohrab Oil Field Well pad Construction (3,4,8) Tender No.: SO-004-00082-03	 DanaEnergy
Rev. 00	Document No. SO-082-DTE-LGN-BD-CFT-0001	Page 50 of 61

Appendix 1 HSE Reports:

1. Daily Report;
2. Weekly Report;
3. Monthly Report (including driven kilometer);
4. Incident Notification Form;
5. Anomaly / Stop Card report;
6. NCR Report;
7. Contractor vehicle information check list;
8. Contractor Cranes Forklifts information checklist.

➤ HSE Monthly Report

		Company: Dana Petro Sohrab		Development and Production Operations Service Contract for Sohrab Oil Field Project										Contractor LOGO													
		Contractor:		HSE Monthly Statistics Report																							
		Reporting Period:																									
				Personal Incident Statistics						Traffic and Fire Incidents				Environmental, Health and Training													
Indicators Contractor/ Scope of work				Number of Personal	Work Hours	Incident to Personal					Total Number of Vehicle Accident	Vehicle Travel (Km)	Number of Vehicle incidents injuries		Vehicle accident frequent Rate (VAFR)	Environme ntal	Health	Burnt Gas (M3)	Training (hours - employee)								
						Slight Injuries	Minor Injuries	Major Injuries	Disability	Death (Fatality)			No of LTI cases	Restricted						Total Number of Day lost	LTI	Frequency rate (FR)	Injury Rate (IR)	Severity Rate (SR)	Loss of Property(\$)	Death	Injured
TOTAL																											
Contractor																											
Sub-Contractors																											

This Performance Report:

Prepared by _____ HSE Supervisor

Checked by _____ QHSE Manager

Approved by _____ Project Manager

* All frequency indicators (LTIF, IR, ISR and VAFR) are calculated for this month only. The Year to date calculation also reports in the MMIR every month

➤ Incident Notification Form

Development and Production Operations Service Contract for Sohrab Oil Field Project									
Incident Notification									
Date of Incident		Time of Incident							
Incident Location									
Incident Party		Activity Function							
Contractor ID & Workscope		description for others							
Person(s) Involved	Name	Date of Birth	Gender	Nationality	Work for	Description of Injury			
Brief Description of the Incident									
Actions Taken After the Incident									
Incident Class	Incident Type				Typical Casual Factors				
Personal Safety					People(Acts)				
Process Safety / Asset Integrity	Loss of Primary Containment (LOPC)								
	Well Blow out								
	Fire&Explosion								
Motor or Vehicle Crash									
Occupational Illness					Process/Condition				
Security	People								
	Facility								
Environment	Loss of Secondary Containment								
	Penalty Fine								
Asset/Property Damage/Loss					Well Control				
Additional Information	Was Emergency Response Required								
	Production/activity shut-down								
	Area closed and evidence secured								
Other					description for others				
Risk Assessment Matrix	Actual Severity		Potential Severity		Potential Likelihood				
People									
Asset									
Environment									
Reputation									
Information of the Reporter	Potential Risk Rating								
Report Date					0				
Report by					1				
Phone No. of the Reporter					2				
Email of the Reporter					3				
Notice:					4				
1. This Notification shall be sent to Company HSE Representative within 24 hour after the incident.					5				
2. If an incident involves a fatality, Company Site Supervisor, Company HSE Representative, Site Manager and Project Manager shall be informed immediately by phone or any other expedient method; and within 2 hour, this Notification shall be emailed to Company HSE Representative as well.									
3. All incidents including Near Miss shall be investigated. An initial incident investigation Report shall be submitted within 7 days for High Potential Incident (HPI), or within 15 days for Significant Incident, and issued to related Project authorized persons for comments and review.									

	Development and Production Operations Service CONTRACT for Sohrab Oil Field Well pad Construction (3,4,8) Tender No.: SO-004-00082-03	 DanaEnergy
Rev. 00	Document No. SO-082-DTE-LGN-BD-CFT-0001	Page 52 of 61

Appendix 2: Minimum HSE Manpower and experience for Construction operations not limited to:

Row	Position	No. Req	Minimum Experience	Minimum Educational Certificate	Remark
1	Head of HSE department	1	10	B.S in HSE	Main Office
2	Environmental HSE expert	1	5	B.S in Environment	Main Office
3	Health HSE expert	1	5	B.S in Health	Main Office
4	Site HSE Manager	1	5	B.S in HSE	On site 24/7.
5	Site HSE Supervisor	1	4	B.S in HSE	On site 24/7.
6	HSE officer	3	3	B.S in HSE	On site 24/7.
7	Road safety officer	4	2	Diploma	On site 24/7.
8	Ambulance Driver	1	3	Diploma and related certificates	On site 24/7.
9	Nurse	1	5	B.S in nursery	On site 24/7.
10	Paramedic	1	3	B.S in nursery	On site 24/7.
11	Fire fighter	2	5	Firefighting related certificates	Call off- On site 24/7.
12	Fire truck Driver	1	5	Diploma Certificate	Call off- On site 24/7.

	Development and Production Operations Service CONTRACT for Sohrab Oil Field Well pad Construction (3,4,8) Tender No.: SO-004-00082-03	 DanaEnergy
Rev. 00	Document No. SO-082-DTE-LGN-BD-CFT-0001	Page 53 of 61

Appendix 3: Minimum activities, responsibilities and services required by a dedicated HSE CONTRACTOR but not limited to:

Row	Description of items	Remarks
1	Patient and injured transportation services	(Air / Ground), Ambulance (Type B+ Dc shock and other related first aid equipment)
2	Rescue Services	(Air / Ground)
3	Personal Protective Equipment	Safety helmet, coverall, safety boots, safety goggles, gloves , respiratory PPE for work with the acid and chemicals, and etc. Full body harness (for Working at Hight).
4	Health care and Medical Services (including rescue equipment)	Dc Shock, AED, Oven, EKG, Clinical Equipment's and Medicines Drinking water health services First Aid Kits and Training Insurance and welfare, Contract with Hospital In case of Emergency Situation. Pre-hire Medical examination services Periodic Medical examination services Approved 3 rd Party inspection For Medical Equipment and issuing the related certificate
5	Harmful factors measurement services	Medic Examination for Employees, Measurement services of Ergonomic, Environment and working area
6	Fire Fighting Services	provide and maintain a foamatic fire truck with require equipment and accessories such as roof top monitor, hose reel (8000-liter water and 2000-liter foam and full equipped with firefighting equipment and tools including but not limited to : 4 No, 60 min. SCBAs, minimum 100 meters Industrial fire houses, Firefighting PPE for all crew, foam and water Nozzles, etc.),with related and standard equipment (according to NFPA,BS and IPS standards) and/or auxiliary trailers, etc. One water Tanker truck (with minimum capacity of 16000 Liters) as backup for Fire Truck. Coordinate with nearest governmental Fire station for Emergency cases Fire Blanket(s) Flash back arrestor(s) Co2 Fire Extinguisher(s) Dry Powder Fire Extinguisher(s) Wheeler 50 and/or 70 kg Dry Powder Fire Extinguisher(s)
7	Oil Spill Services	VACUUM LURRY, pads and etc.

	Development and Production Operations Service CONTRACT for Sohrab Oil Field Well pad Construction (3,4,8) Tender No.: SO-004-00082-03	 DanaEnergy
Rev. 00	Document No. SO-082-DTE-LGN-BD-CFT-0001	Page 54 of 61

8	24 V Lighting and ventilation equipment	As Required for Confide Space Activity- Ex Type
9	Electrical Safety Services	Installing RCCB, grounding (earthing) system, Certified earthing system by approved 3 rd party
10	Lifting inspection Services	Certified Lifting equipment's and machinery by approved 3rd party
11	Waste management Services	Waste and Garbage transportation services
		Sewage transportation , Services and Treatment
		Industrial wastes and sediments
		Hand over the pad and well location
12	HSE and Fire Fighting Training Center	Training Center Class room, PC, Laptop, Printer, The chair, Projector, etc.
13	Legal 3 rd party inspection service for Light and heavy vehicles	Yearly and 6 month per year
14	Radio Communication system	EX-Walkie Talkie and Vehicle Radio base Communication
15	Internet and network	for communication Service and reporting
16	Road safety Controlling system	Provide the adequate safety and warning signs, Traffic Signs Traffic control equipment (Traffic cone, Traffic barrel and etc.) And other required equipment etc.
17	H ₂ S Services and PPE	Escape mask – Personnel H ₂ S Detector (if working in Production or SIMOPS area)

	Development and Production Operations Service CONTRACT for Sohrab Oil Field Well pad Construction (3,4,8) Tender No.: SO-004-00082-03	 DanaEnergy
Rev. 00	Document No. SO-082-DTE-LGN-BD-CFT-0001	Page 55 of 61

Appendix 4 Ambulance Checklist

Ambulance Check list-Type(B) (Iran Standard 4374)

Item	Criteria	Q	Exist?		Remarks
1	Stretcher / stretcher carrier (as per Iran Standard 4370)	1	Y	N	
2	Scope stretcher (as per Iran Standard 4370)	1	Y	N	
3	Vacuum mattress	1	Y	N	
4	Device for conveying a seated patient	1	Y	N	
5	Carrying sheet or transfer mattress	1	Y	N	
6	Long back board	1	Y	N	
7	Traction device	1	Y	N	
8	Splint set	1	Y	N	
9	Collar neck	1	Y	N	
10	Short back board	1	Y	N	
11	Fixed oxygen cylinder with flow meter& with connection means. Minimum capacity to be 2000-liter in normal temperature and normal pressure (equal to 20-liter pressurized oxygen cylinder). The minimum flow rate to be 15 lit/s. (To meet requirements of EN 737-1)	1	Y	N	
12	Portable oxygen cylinder with flow meter& with connection means. Minimum capacity to be 400-liter in normal temperature and normal pressure (equal to 2-liter pressurized oxygen cylinder). The minimum flow rate to be 15 lit/s. (To meet requirements of EN 737-1)	1	Y	N	
13	Ambubag with masks and airways for all ages	1	Y	N	
14	Mouth to mask ventilator with Oxygen inlet	1	Y	N	
15	Electrical medical rechargeable suction (portable or fixed) with minimum 1-lit capacity and with minimum 65 Kilo Pascal negative pressure (To meet requirements of Iranian national Standard No. 4592)	1	Y	N	
16	Portable hand-held suction unit or portable pedal suction unit (To meet requirements of Iranian national Standard No. 4592)	1	Y	N	
17	Manual blood pressure monitor	1	Y	N	
18	Automatic blood pressure monitor	1	Y	N	

	Development and Production Operations Service CONTRACT for Sohrab Oil Field Well pad Construction (3,4,8) Tender No.: SO-004-00082-03	 DanaEnergy
Rev. 00	Document No. SO-082-DTE-LGN-BD-CFT-0001	Page 56 of 61

19	Pulse Oximeter	1	Y	N	
20	Stethoscope	1	Y	N	
21	Medical thermometer with minimum range of 28-42 °C	1	Y	N	
22	Medical penlight	1	Y	N	
23	Blood glucose monitor	1	Y	N	
24	Pain killer medicines (R = amount as required by medical staff or standards)	R	Y	N	
25	Injection solutions (R = amount as required by medical staff or standards)	R	Y	N	
26	Injection set (R = amount as required by medical staff or standards)	R	Y	N	
27	Infusion system for injection of warm liquids in temperatures 37±2	1	Y	N	
28	Serum hanger at proper height for serum injection	2	Y	N	
29	Infusion pump	1	Y	N	
30	Electroshock with rhythm recorder and patient data recorder	1	Y	N	
31	Cardiac monitor	1	Y	N	
32	Portable airway care system + airway with oxygen inlet + hand-held or pedal suction + suction catheter	1	Y	N	
33	Nebulizer	1	Y	N	
34	Chest tube set	1	Y	N	
35	Tools for measurement of injection volume (Like microset)	1	Y	N	
36	Pillow & bed cover	1	Y	N	
37	Blanket	2	Y	N	
38	Bandage set (forceps, sterile gauze, scissors, receiver, gallipot , cotton, shunt)	1	Y	N	
39	Burn bandage set & chemical burn set	1	Y	N	
40	Cold box for Cold box (for keeping amputated limb for at least 2 hours in temperature range of 4±2°C)	1	Y	N	
41	Urine bottle	1	Y	N	
42	Vomiting bag	1	Y	N	

	Development and Production Operations Service CONTRACT for Sohrab Oil Field Well pad Construction (3,4,8) Tender No.: SO-004-00082-03	 DanaEnergy
Rev. 00	Document No. SO-082-DTE-LGN-BD-CFT-0001	Page 57 of 61

43	Stool pan (bed pan)	1	Y	N	
44	Urine bottle (non-glass type)	1	Y	N	
45	Medical Sharps container (waste bin for sharps)	1	Y	N	
46	Nasogastric tube (NG tube)	1	Y	N	
47	Surgical gloves	4	Y	N	
48	Examination latex gloves, disposable, one-time-use type	20	Y	N	
49	Medical waste bin	1	Y	N	
50	Disposable one-time-use stretcher cover (pack)	1	Y	N	
51	Luminescent vest	2	Y	N	
52	Safety clothing (fire resistant)	2	Y	N	
53	Safety gloves (pairs)	2	Y	N	
54	Safety shoes (pairs)	2	Y	N	
55	Safety helmet	2	Y	N	
56	Infection prevention set (mask, cap, ...)	2	Y	N	
57	Cleaning & detergent materials (as required)	1	Y	N	
58	Light rescue tools including rope, fire fighter's axe, crowbar, etc. (each one)	1	Y	N	
59	Harness cutting tool (knife)	1	Y	N	
60	Luminescent danger triangle	2	Y	N	
61	Big flashlight	1	Y	N	
62	Fire extinguisher (EN 3-7)	1	Y	N	
63	Car-mounted radio (for two-way communication)	1	Y	N	
64	Hand-held radio (walkie talkie)	2	Y	N	
65	Telephone communication means (through radio systems or mobile phone)	1	Y	N	
66	Internal communication between driver & patient's cabin	1	Y	N	

	Development and Production Operations Service CONTRACT for Sohrab Oil Field Well pad Construction (3,4,8) Tender No.: SO-004-00082-03	 DanaEnergy
Rev. 00	Document No. SO-082-DTE-LGN-BD-CFT-0001	Page 58 of 61

Appendix 5 Clinic Checklists

CONTRACTOR Clinic Check list

Row	Criteria / item	Exist?		Remarks
Clinic room & accessibility				
1	Adequate space to hold up one bed/stretcher and working space (e.g. table, chairs) plus storage cabinets.	Y	N	
2	Ventilation, illumination, temperature control	Y	N	
3	Refrigerator for certain medicines / drugs	Y	N	
4	Potable water (running or in containers, e.g. bottles)	Y	N	
5	Toilet and shower	Y	N	
6	Hand washing facilities	Y	N	
7	Medical waste disposal system	Y	N	
8	Communication system with site manager and remote working team. Two-way radio communication (Mobile phones or site radios)	Y	N	
9	Easy ingress / egress with stretcher	Y	N	
10	Easy access to ambulance or helipad	Y	N	
11	24 hours on-call availability	Y	N	
Trauma Bag contents				
(I) Ventilation & Airway Equipment				
12	Portable & fixed suction apparatus	Y	N	
13	Wide-bore tubing, rigid pharyngeal curved suction tip; flexible suction catheters	Y	N	
14	Portable/fixed oxygen cylinder with equipment Variable flow	Y	N	
15	Oxygen administration equipment	Y	N	
16	Adequate length tubing; nasal cannulas and masks	Y	N	
17	Pocket mask with one-way valve	Y	N	
18	Bag-valve mask	Y	N	
19	Hand operated, self-expanding bag with oxygen reservoir/	Y	N	
(ii) Airways				
20	Nasopharyngeal, or pharyngeal	Y	N	
21	Laryngoscope handle and blades with extra batteries and bulbs	Y	N	
22	Endotracheal tubes including stylettes for endotracheal tubes	Y	N	
23	Nasogastric tubes	Y	N	
24	Head immobilization device	Y	N	
(iii) Bandages and Sutures				

	Development and Production Operations Service CONTRACT for Sohrab Oil Field Well pad Construction (3,4,8) Tender No.: SO-004-00082-03	 DanaEnergy
Rev. 00	Document No. SO-082-DTE-LGN-BD-CFT-0001	Page 59 of 61

25	Triangular bandages with safety pins	Y	N	
26	Dressings sterile multi-trauma dressings (various large and small sizes) ABDs, 10"x12" or larger	Y	N	
27	4"x4" gauze sponges	Y	N	
28	Gauze rolls sterile (various sizes)	Y	N	
29	Elastic bandages, No sterile (various sizes)	Y	N	
30	Occlusive dressing sterile, 3"x8" or larger	Y	N	
31	Suturing kit including assorted sutures, steristrips, artery forceps, needles, needle holder, etc.	Y	N	
(iv) Medical and Miscellaneous Supplies				
32	Sphygmomanometer (adult regular and large, for example, thigh)	Y	N	
33	Stethoscope	Y	N	
34	Thermometer with low temperature capability	Y	N	
35	Paramedic scissors for cutting clothing, belts, and boots	Y	N	
36	Sterile saline solution for irrigation (1-liter bags)	Y	N	
37	Flashlights (2) with extra batteries and bulbs	Y	N	
38	Triage tags	Y	N	
39	Casualty care charts/ forms/ recording books	Y	N	
40	Tongue depressor	Y	N	
41	Magnifying glass	Y	N	
42	Eye protection (full peripheral glasses or goggles, face shield)	Y	N	
43	Masks	Y	N	
44	Gloves, non-sterile	Y	N	
45	Jumpsuits, disposable gowns	Y	N	
(v) Hand wash& trash bins				
46	Disinfectant hand wash, commercial anti-microbial (novelette,	Y	N	
47	Standard sharps container	Y	N	
48	Disposable trash bags (identifiable color, such as red)	Y	N	
(vi) Vascular Access				
49	Intravenous administration equipment sets (micro drip and macro drip), including pressure bag for IV fluid administration and securing/dressing tape	Y	N	
50	Crystalloid solutions, Ringer's lactate or normal saline solution (1000-ml bags), 5% dextrose in water (optional)	Y	N	
51	Antiseptic solution (alcohol wipes and povidone-iodine wipes preferred)	Y	N	
52	Intravenous catheters assorted sizes	Y	N	
53	Tourniquet, rubber bands	Y	N	

	Development and Production Operations Service CONTRACT for Sohrab Oil Field Well pad Construction (3,4,8) Tender No.: SO-004-00082-03	 DanaEnergy
Rev. 00	Document No. SO-082-DTE-LGN-BD-CFT-0001	Page 60 of 61

54	Syringes for various sizes	Y	N	
55	Needles of various sizes	Y	N	
(vii) Advanced Equipment				
56	Automatic blood pressure device	Y	N	
(viii) Medications				
57	1:10000 epinephrine, atropine, amiodarone, lidocaine, bretylium tosylate, adenosine, diltiazem, diluent	Y	N	
First Aid Kits (for 10-50 persons) to be available around the worksites with following items				
58	Small sterilized dressings (12)	Y	N	
59	Medium sterilized dressings (6)	Y	N	
60	Large sterilized dressings (6)	Y	N	
61	Adhesive wound dressings (24)	Y	N	
62	Triangular bandages (4)	Y	N	
63	1x10 yards zinc oxide plaster	Y	N	
64	2.5 oz sterilized cotton wool (75 grams)	Y	N	
65	Sterilized eye pads (4)	Y	N	
66	Rubber pressure bandage (1)	Y	N	
67	Safety pins (one pkt)	Y	N	
68	Waterproof dressings and plasters	Y	N	
69	Laerdal-type pocket masks (2)	Y	N	
70	PVC gloves (8 pairs)	Y	N	
71	PVC aprons (4)	Y	N	
72	Eye protection (glasses/ goggles)	Y	N	
73	Automatic External Defibrillator, including gel pads	Y	N	
74	Treatment record book	Y	N	

	Development and Production Operations Service CONTRACT for Sohrab Oil Field Well pad Construction (3,4,8) Tender No.: SO-004-00082-03	 DanaEnergy
Rev. 00	Document No. SO-082-DTE-LGN-BD-CFT-0001	Page 61 of 61

Attachment 1: NIOC, COMPANY HSE procedures and checklists:

- 1) NIOC EMS Guideline MOP-HSED-GI-105 (1)
- 2) Safe Journey Management Procedure (SO-000-GMS-HGN-HS-PRC-0013);
- 3) Safety Standard for Light Vehicles (SO-000-GMS-HGN-HS-STD-0003);
- 4) Contractor vehicle information check list;
- 5) Contractor Cranes Forklifts information checklist.